

TRANSMISSION LINE & SUBSTATION PROJECTS

COMPANY:ENTERGY SERVICES, INC.

CUSTOMER: PID 226

FACILITIES STUDY

EJO # F4PPMS0236

GENERATION INTERCONNECTION FACILITIES STUDY

<u>PID226</u>

Revision:

Rev	lssue Date	Description of Revision	Prepared By	Approved By
А	09/09/09	1 st Draft	JWM	CN
В	09/09/09	2 nd Draft to JET Members	JWM	CN
0	09/10/09	Approved Issue	JWM	CN
1	09/28/09	TPD Review	RB	BW
2	10/9/09	ICT Review and Classification	BEF	JDH
3A	01/19/10	Additional Item's 7-12 Draft by Project	JWM	CN
3B	02/15/10	Item's 7-12 Approved Issue	JWM	CN
3C	02/16/10	TPD	JRB	BW
3	2/26/10	ICT Review and Upgrade Classification	MEC	JDH
4	03/5/10	Report Edited to Include Stability Study	MEC	JDH
5	3/25/10	Revised and Posted	HDE	JDH

TABLE OF CONTENTS

PROJECT SUMMARY4
1.1 Background and Project Need 4
1.2 Scope Summary
1.3 Cost Summary5
1.4 Schedule Summary
SAFETY REQUIREMENTS6
GENERAL ASSUMPTIONS7
SCOPE OF WORK7
4.1 Rolling Fork 115kV Substation: Install 21.6MVAR Capacitor Bank
4.2 Yazoo City Municipal115kV Substation: Install 21.6MVAR Capacitor Bank
4.3 Carthage 115kV Substation: Install 21.6MVAR Capacitor Bank
4.4 Tylertown 115kV Substation: Install 21.6MVAR Capacitor Bank 11
4.5 Magee 115kV Substation: Install a second 32.4MVAR Capacitor Bank 12
4.6 McComb 115kV Substation: Upgrade one of the 21.6MVAR capacitor banks to 32.4MVAR
4.7 Item 7 - Senatobia 115kV Substation: Install 21.6MVAR Capacitor Bank 13
4.8 Item 8 - Plum Point 115kV Substation: Install 21.6MVAR Capacitor Bank 15
4.9 Item 9 - Hernando 115kV Substation: Split the existing 32.4MVAR bank into two (2) 21.6MVAR Capacitor Banks
4.10 Item 10 - Hollandale 115kV Substation: Split the existing 32.4MVAR bank into two (2) 21.6MVAR Capacitor Banks
4.11 Item 11 - Port Gibson 115kV Substation: Split the existing 32.4MVAR bank into two (2) 21.6MVAR Capacitor Banks
4.12 Item 12 - Fayette 115kV Substation: Split the existing 32.4MVAR bank into two (2) 21.6MVAR Capacitor Banks
COST
SCHEDULE
RISK ASSESSMENT
CONFIRMED RESERVATIONS
ATTACHMENTS

PROJECT SUMMARY

1.1 Background and Project Need

The purpose of this Facilities Study is to evaluate the impact of uprating the existing generation at Grand Gulf Nuclear by 206MW. The net output at Grand Gulf is presently 1287MW (1157MW EMO designated network resource and 130MW SMEPA designated network resource). After the 206MW uprate, the net output at Grand Gulf will be 1493MW.

PID 226 only requested ERIS. Upgrades were identified for ERIS.

According to the FERC Large Generator Interconnection Agreement (LGIA), a generator interconnection customer is required to be capable of supplying at least 0.33 MVAR for each MW of power injected into the grid, in order to meet the specified 0.95 power factor requirement. When Grand Gulf is serving maximum power at 1503.5MW and 547.25MVAR, the power factor at the generator terminals is 0.940. After accounting for MW and MVAR losses in the customer's 500/20.9kV step-up transformer, the power reaching the POI is approximately 1443MW and 260MVAR, corresponding to a 0.979 power factor. In order to meet the LGIA power factor design criteria, 216MVAR of additional capacitor bank installations and upgrades are required.

Due to the large amount of reactive power support required, it is not feasible to place the capacitor banks at the generator terminal. Consequently, for this particular generator interconnection, it is more advantageous in terms of system reliability for distributed capacitor bank placements at the load centers. The conclusive findings of the attached Stability Analysis demonstrate that PID 226's 206MW uprate would not have any adverse impact on the Entergy transmission grid. The results of the revised stability study (performed as a part of the Facilities Study) with the updated stability data show that the proposed generator uprate from PID 226 was stable, both with and without Power System Stabilizer (PSS).


1.2 Scope Summary

- The overall scope of this project is summarized as follows:
 - Install a 21.6MVAR capacitor bank at Rolling Fork 115kV.
 - Install a 21.6MVAR capacitor bank at Yazoo City Municipal 115kV.
 - Install a 21.6MVAR capacitor bank at Carthage 115kV.
 - Install a 21.6MVAR capacitor bank at Tylertown 115kV.
 - Install a 2nd capacitor at Magee 115kV, sized at 32.4MVAR.
 - Upgrade one of the 21.6MVAR capacitor banks at McComb 115kV to 32.4MVAR.

Revision 1; January 19, 2010 Additional items 7-12

- Install a 21.6MVAR capacitor bank at **Senatobia** 115kV.
- Install a 21.6MVAR capacitor bank at **Plum Point** 115kV.
- Split the existing 32.4MVAR capacitor bank at **Hernando** 115kV into two 21.6MVAR capacitor banks.
- Split the existing 32.4MVAR capacitor bank at **Hollandale** 115kV into two 21.6MVAR capacitor banks.
- Split the existing 32.4MVAR capacitor bank at **Port Gibson** 115kV into two 21.6MVAR capacitor banks.
- Split the existing 32.4MVAR capacitor bank at **Fayette**115kV into two 21.6MVAR capacitor banks.

2010 - 2012 Capacitor Bank Projects Location map Supporting PID 226 and GGU



1.3 Cost Summary

- The estimated total cost on projects presently not in construction is **\$9,895,877.00.** This cost does not include Tax Gross Up which may apply. This is a good faith 20% estimate based on current conditions and the time frame allowed to complete the study.
- The ICT has assigned **<u>\$9,895,877.00</u>** as Supplemental Upgrades based on Attachment "T" of Entergy's ICT (Independent Coordinator of Transmission) filing to the FERC.

Project/Station Description	Total Project	Construction Start	Construction Finish
Item 8 Plum Point 115kV Substation	\$914,649.00	August 16,2010	February 07, 2011
Item 9 Hernando 115kV Substation	\$1,112,844.00	Sept. 13, 2010	February 28, 2011
Item 7 Senatobia 115kV Substation	\$1,023,537.00	October 18,2010	March 21,2011
Item 10 Hollandale 115kV Substation	\$1,121,269.00	November 15,,2010	April 11,2011
Rolling Fork 115kV Substation	\$652,418.00	January 24, 2011	April 07,2011
Yazoo City Municipal 115kV Sub.	\$617,916.00	2011, February 21	May 23,2011
Carthage 115kV Substation	\$844,708.00	February 07, 2011	June 13,2011
Tylertown 115kV Substation	\$900,297.00	March 07,2011	October 14,2011
Item 12 Fayette 115kV Substation	\$1,034,502.00	April 18,2011	November 07,2011
Item 11 Port Gibson 115kV Substation	\$940,922.00	May 31, 2011	November 30, 2011
McComb 115kV Substation	\$75,970.00	August 22, 2011	January 11, 2011
Magee 115kV Substation	\$656,843.00	August 22, 2011	December 28, 2011

1.4 Schedule Summary

NOTE: Projects 1-12 In Service Dates are based on a <u>preliminary, non-</u> <u>constrained (unbaselined) project schedules</u>, and include significant schedule assumptions, such as timing of funding authorization(s), outage approvals, ROW/permitting, etc.

Also, the dates above are construction start dates and *not* design package delivery dates. See the Construction area in Blue in the schedule attached in section 9.4

Automatic Generation Control

 Upgrades required by Entergy for AGC service are discussed in Entergy's OASIS posting "Entergy Transmission Guidelines for Automatic Generator Control Applications". See link below:

http://oasis.e-terrasolutions.com/documents/EES/AGC%20Guidelines%20for%20Entergy%20Transmission.pdf

SAFETY REQUIREMENTS

Safety is a priority with Entergy. Safety will be designed into substations and lines. The designs will be done with the utmost safety for personnel in mind for construction, operation, and maintenance of the equipment.

All employees working directly or indirectly for Entergy shall adhere to all rules and regulations outlined within the Entergy Safety manual. Entergy requires safety to be the highest priority for all projects. All Entergy and Contract employees must follow all applicable safe work procedures.

Should the work contained within this Facilities Study be approved, a detailed Safety Plan will be formulated and incorporated within the project plan.

GENERAL ASSUMPTIONS

A common assumption across all projects is that adequate space is available in all substation sites. When necessary work order specific assumptions will be included in the scope of work section below; otherwise

- Upon receipt of formal approval from customer authorizing design and construction, Entergy will prepare a detailed project execution plan with a definitive baselined schedule for each project.
- Where necessary wetland mitigation and SWPPP cost will be included in the work order scope of work.
- All permits will be attainable in a reasonable period.
- Due to timing and/or funding constraints, site visits, surveys, and soil borings were not performed in order to develop this facility study.
- All costs above represent good faith estimates in today's dollars. Price escalation for work in future years has not been included.
- Assumptions to meet a **March 1, 2012** in-service date on all projects is based on internal/external labor resources and funding availability allowing for executions of designs, material ordering and construction resources to be acquired in a timely manner.
- All Class 3 estimates are based on EMCC PERI Guidelines.

SCOPE OF WORK

4.1 Rolling Fork 115kV Substation: Install 21.6MVAR Capacitor Bank

Site Work

No Site Work Required.

Foundations

The following foundations are required. Foundation design will be based on existing foundations.

Install one (1) 115kV 21MVAR Capacitor Bank foundation

Install one (1) 115kV Cap Switcher Foundation

Install one (1) 115kV CE Tower foundation

Install three (3) 115kV Equipment Pedestal foundations

Electrical

Install one (1) fuseless 115 kV 21.6MVAR ungrounded wye capacitor bank. There are two parallel strings in each phase. Six (6) capacitor units in series and each capacitor has six (6) internal sections, giving 36 series sections per string. Each capacitor can has a rating of 600kVAR.

Install one (1) CE switch structure of 16ft.

Install one (1) Southern States Cap Switcher with pre-insertion resistor that includes its support structure (115kV, 1200A continuous rating). Install one (1) vertical break disconnect switch (mounted on new CE tower).

Install three (3) new CVTs and their support structures between switch and Cap Switcher.

Relay and Settings Work

Capacitor Bank Control:

Install one (1) Capacitor Bank Control Panel The panel will use a SEL-451.

Install three (3) CVT, 115kV

Install one (1) Junction Box, CVT, Termination, Cable

Install one (1) Neutral PT

Install one (1) Neutral PT Junction Box, Termination, Cable Settings will need to be derived for one capacitor bank control panel consisting of one SEL 451 relay.

Control House Equipment:

Upgrade RTU to MEII - Status cards & Control cards Install one (1) Orion 5R Install one(1) GPS SEL2407 One lot of control cable

Communications and SCADA Work

Existing M microprocessor board and Harris protocol - upgrade needed for this.

4.2 Yazoo City Municipal115kV Substation: Install 21.6MVAR Capacitor Bank

Site Work

No Site Work Required.

Foundations

The following foundations are required. Foundation design will be based on existing foundations.

Install six (6) 115kV Bus Support Foundation

Install one (1) 115kV 21MVAR Capacitor Bank foundation

Install one (1) 115kV Cap Switcher Foundation

Install one (1) 115kV CE Tower foundation

Install three (3) 115kV Equipment Pedestal foundations

Electrical

Install one (1) fuseless 115 kV 21.6MVAR ungrounded wye capacitor bank. There are two parallel strings in each phase. Six (6) capacitor

units in series and each capacitor has six (6) internal sections, giving 36 series sections per string. Each capacitor can has a rating of 600kVAR.

Install one (1) CE switch structure of 16ft.

Install one (1) Southern States Cap Switcher with pre-insertion resistor that includes its support structure (115kV, 1200A continuous rating). Install one (1) vertical break disconnect switch (mounted on new CE tower).

Install three (3) new CVTs and their support structures between switch and Cap Switcher.

Install six (6) new bus support structures with insulators.

Relay and Settings Work

Capacitor Bank Control:

Install one (1) Capacitor Bank Control Panel The panel will use a SEL-451.

Install three (3) CVT, 115kV

Install one (1) Junction Box, CVT, Termination, Cable

Install one (1) Neutral PT

Install one (1) Neutral PT Junction Box, Termination, Cable Settings will need to be derived for one capacitor bank control panel consisting of one SEL 451 relay.

Control House Equipment:

Upgrade RTU - Status cards & Control cards Install one (1) Orion 5R Install one (1) GPS SEL2407 One Lot of Control Cable

Communications and SCADA Work

Existing microprocessor board and 8979 protocol – no upgrade at this time needed.

4.3 Carthage 115kV Substation: Install 21.6MVAR Capacitor Bank

Site Work

Significant site work will be required to expand the substation in order to accommodate the new capacitor bank. There is approximately 4' change in elevation in the new portion of the substation. Expand the Northeast corner of the substation by approximately 12,000 sq ft (84' to the east, 55' to the north, and 65' to the south.) The following materials are required to complete the site work:

2000 cu yds of fill

250 cu yds of soil stripping and disposal

1 acre seeded and mulched

110 ft of existing fence removal

358 ft of new fence

Foundations

The following foundations are required. Foundation design will be based on existing foundations.

Install twelve (12) 115kV Bus Support Foundations Install one (1) 115kV 21MVAR Capacitor Bank foundation Install one (1) 115kV Cap Switcher Foundation

Install one (1) 115kV CE Tower foundation

Install three (3) 115kV Equipment Pedestal foundations

Electrical

Install one (1) fuseless 115 kV 21.6MVAR ungrounded wye capacitor bank. There are two parallel strings in each phase. Six (6) capacitor units in series and each capacitor has six (6) internal sections, giving 36 series sections per string. Each capacitor has a rating of 600kVAR.

Install one (1) CE switch structure of 16ft.

Install one (1) Southern States Cap Switcher with pre-insertion resistor that includes its support structure (115kV, 1200A continuous rating). Install one (1) vertical break disconnect switch (mounted on new CE tower).

Install three (3) new CVTs and their support structures between switch and Cap Switcher.

Install twelve (12) new bus support structures with insulators.

Relay and Settings Work

Capacitor Bank Control:

Install one (1) Capacitor Bank Control Panel The panel will use a SEL-451.

Install three (3) CVT, 115kV

Install one (1) Junction Box, CVT, Termination, Cable

Install one (1) Neutral PT

Install one (1) Neutral PT Junction Box, Termination, Cable

Install one (1) Trap – Capbank

Settings will need to be derived for one capacitor bank control panel consisting of one SEL 451 relay.

Control House Equipment:

Upgrade RTU to MEII - Status cards & Control cards Install one (1) Orion 5R One Lot of Control Cable

Communications and SCADA Work

Existing M++ microprocessor board and Harris protocol - upgrade needed for this.

4.4 Tylertown 115kV Substation: Install 21.6MVAR Capacitor Bank

Site Work

Significant site work will be required to expand the substation in order to accommodate the new capacitor bank. There is approximately 6' change in elevation in the new portion of the substation. Expand the northern most corner of the substation by 13,000 sq ft (41' to the West, 103' to the North, and 74' to the East.)

The following materials are required to complete the site work: 3500 cu yds of fill 300 cu yds of soil stripping and disposal 1 acre seeded and mulched 106 ft of existing fence removal 394 ft of new fence

Foundations

The following foundations are required. Foundation design will be based on existing foundations.

Install twelve (12) 115kV Bus Support Foundations

Install one (1) 115kV 21MVAR Capacitor Bank foundation

Install one (1) 115kV Cap Switcher Foundation

Install one (1) 115kV CE Tower foundation

Install three (3) 115kV Equipment Pedestal foundations

Electrical

Install one (1) fuseless 115 kV 21.6MVAR ungrounded wye capacitor bank. There are two parallel strings in each phase. Six (6) capacitor units in series and each capacitor has six (6) internal sections, giving 36 series sections per string. Each capacitor can has a rating of 600kVAR.

Install one (1) CE switch structure of 16ft.

Install one (1) Southern States Cap Switcher with pre-insertion resistor that includes its support structure (115kV, 1200A continuous rating). Install one (1) vertical break disconnect switch (mounted on new CE tower).

Install three (3) new CVTs and their support structures between switch and Cap Switcher.

Install twelve (12) new bus support structures with insulators.

Relay and Settings Work

Capacitor Bank Control:

Install one (1) Capacitor Bank Control Panel The panel will use a SEL-451.

Install three (3) CVT, 115kV. Install one (1) Junction Box, CVT, Termination, Cable Install one (1) Neutral PT Settings will need to be derived for one capacitor bank control panel consisting of one SEL 451 relay.

Control House Equipment:

Upgrade RTU to MEII - Status cards & Control cards Install one (1) Orion 5R Install one (1) GPS SEL2407 One Lot of Control Cable

Communications and SCADA Work

Existing M microprocessor board and 8979 protocol - upgrade needed for this.

4.5 Magee 115kV Substation: Install a second 32.4MVAR Capacitor Bank

Site Work

No Site Work Required.

Foundations

The following foundations are required. Foundation design will be based on existing foundations.

Install one (1) 115kV 32.4MVAR Capacitor Bank foundation.

Install one (1) 115kV Cap Switcher Foundation.

Install one (1) 115kV CE Tower foundation.

Install three (3) 115kV Equipment Pedestal foundations.

Electrical

Install one (1) fuseless 115 kV 32.4MVAR ungrounded wye capacitor bank. There are two parallel strings in each phase. Six (6) capacitor units in series and each capacitor has six (6) internal sections, giving 36 series sections per string. Each capacitor can has a rating of 600kVAR.

Install one (1) CE switch structure of 16ft.

Install one (1) Southern States Cap Switcher with pre-insertion resistor that includes its support structure (115kV, 1200A continuous rating). Install one (1) vertical break disconnect switch (mounted on new CE tower).

Install three (3) new CVTs and their support structures between switch and Cap Switcher.

Install an additional pre-insertion resistor on existing Mark IV.

Relay and Settings Work

Capacitor Bank Control:

Install one (1) Capacitor Bank Control Panel The panel will use a SEL-451.

Install three (3) CVT, 115kV.

Install one (1) Junction Box, CVT, Termination, Cable.

Install one (1) Neutral PT.

Install one (1) Neutral PT Junction Box, Termination, Cable. Settings will need to be derived for one capacitor bank control panel consisting of one SEL 451 relay.

Control House Equipment:

Upgrade RTU to MEII - Status cards & Control cards. Install one (1) Orion 5R. Install one (1) GPS SEL2407. One Lot of Control Cable.

Communications and SCADA Work

Existing M+ microprocessor board and 8979 protocol - upgrade needed for this.

4.6 McComb 115kV Substation: Upgrade one of the 21.6MVAR capacitor banks to 32.4MVAR

Site Work

No Site Work Required.

Foundations

No Site Work Required.

Electrical

The existing 21.6MVAR capacitor bank will be up graded to 32.4MVAR's by adding an addition 18 cans, rated at 600kVAR each.

Relay and Settings Work

Settings will need to be derived for capacitor bank control panel consisting of one ZIV relay.

4.7 Item 7 - Senatobia 115kV Substation: Install 21.6MVAR Capacitor Bank

Site Work

There are minor elevation changes in the area of expansion. Assume the top 12" of soil will need to be stripped and replaced with fill material. The site work will require the following materials:

500 cu yds of fill dirt 500 cu yds of cut 1 acre of seed and mulch 250 ft of new fence 110 ft of removal of existing fence

Foundation Work

The following foundations will need to be installed totaling 31 cu yards of concrete:

One (1) 3 phase capacitor bank foundation

One (1) 115kV Cap switcher foundation

Nine (9) 115kV Low elevation bus support foundations

One (1) 115kV Low elevation switch support foundation

Three (3) 115kV Tubular CVT support foundations

Install approximately 1600 ft of grounding to expand the station Install approximately 2180 ft of conduit.

Install one (1) Pull box

Steel and Electrical Work

Capacitor Bank Bay

- Install one (1) Shunt, Fuseless, 115kV; 21.6MVAR Capacitor Bank connected ungrounded wye. This bank will have a rated voltage of 118.47kV. It will consist of six (6) cans in each series section (each capacitor has six (6) internal sections), and two (2) series in parallel per phase, which is a total of 36 series sections per string. Each capacitor unit is rated 11.4kV, 600kvVAR per can.
 - Install one (1) 69kV Neutral PT and junction box (both ordered by relay designer) which will be mounted on the capacitor bank.
- Install three (3) CVT Support Structures
- Install three (3) CVTs (ordered by relay designer) in between the vertical break switch and cap switcher. They will be mounted on CVT Support Structures
- Install one (1) 123kV, 550kV BIL, 650A Southern States Cap Switcher with a 150Ω Pre-Insertion Resistor, which has a Primary Fault Interrupting Current of 40kA.
- Install one (1) "ČE" 16' Switch Tower (DWG# SSCETW01)
- Install one (1) 115kV, 2000A Vertical Break Disconnect Switch with a Motor Operator mounted on the "CE" Tower
 Install nine (9) porcelain insulators (TR#286) on switch
- Install 180' of 336 ACSR (Linnet) for the jumpers to connect above equipment

<u>115kV Bus</u>

- Install nine (9) 13' lally columns to extend the 115kV Operating bus to the north
 - Install nine (9) porcelain insulators mounted on new lally columns

- Install approx. 250' of 2½" Sch. 40 aluminum to extend the 115kV Operating Bus and approx. 42' of 1½" Sch. 40 aluminum for the A-Frames
 - To minimize outages, the bus should include splices in between the existing bus and new bus that will be installed.
- Install approx. 250' of 336 ACSR (Linnet) for bus damping
- Install one (1) yard light

Relay and Settings Work

Capacitor Bank Control:

Install one (1) 48VDC Capacitor Bank Control Panel The panel will use a SEL-451. Install three (3) CVT, 115kv Install one (1) Junction Box, CVT, Termination, Cable Install one (1) Neutral PT Install one (1) Neutral PT Junction Box, Termination, Cable Install one (1) Neutral PT Junction Box, Termination, Cable Install one (1) Line Trap Settings will need to be derived for one capacitor bank control panel consisting of one SEL 451 relay.

Control House Equipment: Upgrade RTU - Status cards & Control cards Install one (1) Orion. One Lot of Control Cable

Communications and SCADA Work

This RTU will be upgraded to MEII/8979 this year (Mike Hendrix is doing this project). Sufficient capacity for a typical capacitor bank addition exists.

4.8 Item 8 - Plum Point 115kV Substation: Install 21.6MVAR Capacitor Bank Site Work

No Site work is required. Small amount of limestone to replace around new foundations:

100 tons of limestone

Foundation Work

The following foundations will need to be installed totaling 31 cu yards of concrete:

One (1) 3 phase capacitor bank foundation

One (1) 115kV Cap switcher foundation

Nine (9) 115kV Low elevation bus support foundations

One (1) 115kV Low elevation switch support foundation

Three (3) 115kV Tubular CVT support foundations

Install approximately 1300 ft of grounding to expand the station Install approximately 1850 ft of conduit Install one (1) Pull box

Steel and Electrical Work

Capacitor Bank Bay

- Install one (1) Shunt, Fuseless, 115kV; 21.6MVAR Capacitor Bank connected ungrounded wye. This bank will have a rated voltage of 118.47kV. It will consist of six (6) cans in each series section (each capacitor has six (6) internal sections), and two (2) series in parallel per phase, which is a total of 36 series sections per string. Each capacitor unit is rated 11.4kV, 600kVAR per can.
 - Install one (1) 69kV Neutral PT and junction box (both ordered by relay designer) which will be mounted on the capacitor bank.
- Install three (3) CVT Support Structures.
- Install three (3) CVTs (ordered by relay designer) in between the vertical break switch and cap switcher. They will be mounted on CVT Support Structures.
- Install one (1) 123kV, 550kV BIL, 650A Southern States Cap Switcher with a 150Ω Pre-Insertion Resistor, which has a Primary Fault Interrupting Current of 40kA.
- Install one (1) "CE" 16' Switch Tower (DWG# SSCETW01).
- Install one (1) 115kV, 2000A Vertical Break Disconnect Switch with a Motor Operator mounted on the "CE" Tower.
 - o Install nine (9) porcelain insulators (TR#286) on switch
- Install 120' of 336 ACSR (Linnet) for the jumpers to connect above equipment.

<u>115kV Bus</u>

- Install nine (9) 13' lally columns to extend the 115kV Operating bus to the north.
 - Install nine (9) porcelain insulators mounted on new lally columns.
- Install approx. 230' of 2½" Sch. 40 aluminum to extend the 115kV Operating Bus and approx. 42' of 1½" Sch. 40 aluminum for the A-Frames.
 - To minimize outages, the bus should include splices in between the existing bus and new bus that will be installed.
 - Install approx. 230' of 336 ACSR (Linnet) for bus damping.
- Install one (1) yard light.

Relay and Settings Work

Capacitor Bank Control:

Install one (1) Capacitor Bank Control Panel. The panel will use a SEL-451.

Install three (3) CVT, 115kv

Install one (1) Junction Box, CVT, Termination, Cable

Install one (1) Neutral PT

Install one (1) Neutral PT Junction Box, Termination, Cable Settings will need to be derived for one capacitor bank control panel consisting of one SEL 451 relay.

Control House Equipment:

Upgrade RTU - Status cards & Control cards Install one (1) Orion Comm Pro. Install one(1) GPS SEL2407 One Lot of Control Cable

Communications and SCADA Work

This RTU will be upgraded to MEII/8979 this year (Mike Hendrix is doing this project). Sufficient capacity for a typical capacitor bank addition exists.

4.9 Item 9 - Hernando 115kV Substation: Split the existing 32.4MVAR bank into two (2) 21.6MVAR Capacitor Banks

Site Work

There is a significant change in elevation of approximately 5' in the area of expansion. Assume 12" of topsoil will be stripped. The following material will be required to complete the site work:

600 cu yds of fill dirt

100 cu vds of cut

1 acre of seed and mulch

190 ft of new fence

110 ft of removal of existing fence

Foundation Work

The following foundations will need to be installed totaling 31 cu yards of concrete:

One (1) 3 phase capacitor bank foundation

One (1) 115kV Cap switcher foundation

Nine (9) 115kV Low elevation bus support foundations

One (1) 115kV Low elevation switch support foundation

Three (3) 115kV Tubular CVT support foundations

Install approximately 1650 ft of grounding to expand the station Install approximately 2450 ft of conduit Install one (1) Pull box

Steel and Electrical Work

Existing Capacitor Bank Bay

The existing bank is a fused 31.5MVAR bank. Each can is rated about 150kVAR. It has five (5) parallel groups with 14 cans each. 150kVAR * 14(cans) * 5(parallel) * 3(phases) = 31.5MVAR

- So we will remove five (5) cans per group to get 20.25MVAR which is 1.35MVAR less than the desired 21.6MVAR.
 - 150kVAR * 9(cans) * 5(parallel) * 3(phases) = 20.25MVAR

New 21.6MVAR Capacitor Bank Bay

- Install one (1) Shunt, Fuseless, 115kV, 21.6MVAR Capacitor Bank connected ungrounded wye. This bank will have a rated voltage of 118.47kV. It will consist of six (6) cans in each series section (each capacitor has six (6) internal sections), and two (2) series in parallel per phase, which is a total of 36 series sections per string. Each capacitor unit is rated 11.4kV, 600kVAR per can.
 - Install one (1) 69kV Neutral PT and junction box (both ordered by relay designer) which will be mounted on the capacitor bank.
- Install three (3) CVT Support Structures
- Install three (3) CVTs (ordered by relay designer) in between the vertical break switch and cap switcher. They will be mounted on CVT Support Structures.
- Install one (1) 123kV, 550kV BIL, 650A Southern States Cap Switcher with a 150Ω Pre-Insertion Resistor, which has a Primary Fault Interrupting Current of 40kA.
- Install one (1) "CE" 16' Switch Tower (DWG# SSCETW01)
- Install one (1) 115kV, 2000A Vertical Break Disconnect Switch with a Motor Operator mounted on the "CE" Tower.
 - Install nine (9) porcelain insulators (TR#286) on switch
- Install 120' of 336 ACSR (Linnet) for the jumpers to connect above equipment
- <u>115kV Bus</u>
- Install nine (9) 13' lally columns to extend the 115kV Operating bus to the north
 - Install nine (9) porcelain insulators mounted on new lally columns
- Install approx. 230' of 2½" Sch. 40 aluminum to extend the 115kV Operating Bus and approx. 42' of 1½" Sch. 40 aluminum for the A-Frames
 - \circ $\,$ To minimize outages, the bus should include splices in
 - between the existing bus and new bus that will be installed.
- Install approx. 230' of 336 ACSR (Linnet) for bus damping
- Install one (1) yard light

Relay and Settings Work

Capacitor Bank Control:

Install one (1) 48VDC OUTDOOR dual Capacitor Bank Control Panel. The panel will use a SEL-451. Install three (3) CVT, 115kV Install one (1) Junction Box, CVT, Termination, Cable Install one (1) Neutral PT Install one (1) Neutral PT Junction Box, Termination, Cable Settings will need to be derived for one capacitor bank control panel consisting of one SEL 451 relay.

Control House Equipment:

Upgrade RTU - Status cards & Control cards Install one (1) Orion Comm Pro One Lot of Control Cable

Communications and SCADA Work

This RTU will be upgraded to MEII/8979 this year (Mike Hendrix is doing this project). Sufficient capacity for a typical capacitor bank addition exists.

4.10 Item 10 - Hollandale 115kV Substation: Split the existing 32.4MVAR bank into two (2) 21.6MVAR Capacitor Banks

Site Work

Expansion of the substation area won't require much fill as the land looks relatively flat. Assume 12" of topsoil will be stripped. The following materials are required to complete the site work:

200 cu yds of fill dirt 200 cu yds of cut 1 acre of seed and mulch 320 ft of new fence 160 ft of removal of existing fence

Foundation Work

The following foundations will need to be installed totaling 31 cu yards of concrete:

One (1) 3 phase capacitor bank foundation

One (1) 115kV Cap switcher foundation

One (1) 115kV Transformer "A" Tower deadend

One (1) 115kV Low elevation switch support foundation Three (3) 115kV Tubular CVT support foundations

Install approximately 2000 ft of grounding to expand the station Install approximately 3600 ft of conduit.

Install two (2) Pull boxes

Steel and Electrical Work

Existing Capacitor Bank Bay

 The existing bank is a General Electric Fuseless 32.4MVAR bank with a rated voltage of 118.47kV. Each can is rated about 600kVAR. It has three (3) parallel groups with six (6) cans each, a total of 54 cans.

600kVAR * 6(cans) * 3(parallel) * 3(phases) = 32.4MVAR

- So we will remove one (1) series in parallel group (6 cans) per phase to get the desired 21.6MVAR, leaving a total of 36 cans.
 o 600kV * 6(cans) * 2(parallel) * 3(phases) = 21.6MVAR
- The existing Interrupting Device for the cap bank is an S&C Mark V with no pre-insertion device, so in order to lower the back-toback switching current transients to levels that are acceptable, a 40mH, 5.5Ω Standard-Duty Pre-Insertion Inductor will need to be installed on this Circuit Switcher.

New 21.6MVAR Capacitor Bank Bay

- Install one (1) Shunt, Fuseless, 115kV, 21.6MVAR Capacitor Bank connected ungrounded wye. This bank will have a rated voltage of 118.47kV. It will consist of six (6) cans in each series section (each capacitor has six (6) internal sections), and two (2) series in parallel per phase, which is a total of 36 series sections per string. Each capacitor unit is rated 11.4kV, 600kVAR per can.
 - Install one (1) 69kV Neutral PT and junction box (both ordered by relay designer) which will be mounted on the capacitor bank.
- Install three (3) CVT Support Structures
- Install three (3) CVTs (ordered by relay designer) connected to the bus via jumpers. They will be mounted on CVT Support Structures
- Install one (1) 123kV, 550kV BIL, 650A Southern States Cap Switcher with a 150Ω Pre-Insertion Resistor, which has a Primary Fault Interrupting Current of 40kA.
- Install one (1) "CE" 16' Switch Tower (DWG# SSCETW01)
- Install one (1) 115kV, 2000A Vertical Break Disconnect Switch with a Motor Operator mounted on the "CE" Tower
- Install nine (9) porcelain insulators (TR#286) on switch
 Install 150' of 336 ACSR (Linnet) for the jumpers to connect above equipment

<u>115kV Bus</u>

- Install one (1) "A" Tower in between the Greenville line coming in and Switch #J0491.
 - Install six (6) 115kV Suspension Insulators, 3 on each side of the "A" Tower
- Install one (1) 115kV, 2000A Vertical Break, Three Phase Disconnect Switch with a Motor Operator mounted on the "A" Tower.
 - Install nine (9) porcelain insulators (TR#286) on switch
 - This switch should also include a LLS Interrupting Device along with a Ground Switch (when ordering this ground

switch, make sure that the hand crank pipe is long enough because the "A" Tower is significantly taller than the "CE" Tower which is typically used as a switch support.)

- Install approx. 300' of 336 ACSR (Linnet) to extend the bus and tap off of the Greenville line side in order to install the new Cap Bank Bay.
- Install one (1) yard light

Relay and Settings Work

Capacitor Bank Control:

Install two (2) 48VDC OUTDOOR Capacitor Bank Control Panel. The panel will use a SEL-451. Install three (3) CVT, 115kv Install one (1) Junction Box, CVT, Termination, Cable Install one (1) Neutral PT Install one (1) Neutral PT Junction Box, Termination, Cable Settings will need to be derived for one capacitor bank control panel consisting of one SEL 451 relay. Control House Equipment:

Upgrade RTU - Status cards & Control cards Install one (1) Orion One Lot of Control Cable

Communications and SCADA Work

This RTU will be upgraded to MEII/8979 this year (Mike Hendrix is doing this project). Sufficient capacity for a typical capacitor bank addition exists.

4.11 Item 11 - Port Gibson 115kV Substation: Split the existing 32.4MVAR bank into two (2) 21.6MVAR Capacitor Banks

Site Work

The land appears relatively flat from the pictures we have available. The expanded area will need to accommodate both capacitor banks.

The following material will be required to complete the site work: 250 cu yds of fill dirt

150 cu yds of cut

1 acre seed and mulch

250 ft of new fence

110 ft of removal of existing fence

Foundation Work

The following foundations will need to be installed totaling 31 cu yards of concrete:

One (1) 3 phase capacitor bank foundation

One (1) 115kV Cap switcher foundation

Nine (9) 115kV Low elevation bus support foundations One (1) 115kV Low elevation switch support foundation Three (3) 115kV Tubular CVT support foundations Install approximately 1500 ft of grounding to expand the station Install approximately 1690 ft of conduit Install one (1) Pull box

Steel and Electrical Work

Existing Capacitor Bank Bay

- The existing bank is a General Electric Fuseless 32.4MVAR bank with a rated voltage of 118.47kV. Each can is rated about 600kvVAR. It has three (3) parallel groups with six (6) cans each, a total of 54 cans.
 - 600kVAR * 6(cans) * 3(parallel) * 3(phases) = 32.4MVAR
- So we will remove one (1) series in parallel group (6 cans) per phase to get the desired 21.6MVAR, leaving a total of 36 cans.
 o 600kVAR * 6(cans) * 2(parallel) * 3(phases) = 21.6MVAR

New 21.6MVAR Capacitor Bank Bay

- Install one (1) Shunt, Fuseless, 115kV, 21.6MVAR Capacitor Bank connected ungrounded wye. This bank will have a rated voltage of 118.47kV. It will consist of 6 cans in each series section (each capacitor has 6 internal sections), and 2 series in parallel per phase, which is a total of 36 series sections per string. Each capacitor unit is rated 11.4kV, 600kVAR per can.
 - Install one (1) 69kV Neutral PT and junction box (both ordered by relay designer) which will be mounted on the capacitor bank.
- Install three (3) CVT Support Structures
- Install three (3) CVTs (ordered by relay designer) which will be connected to the 115kV Transfer bus. They will be mounted on CVT Support Structures
- Install one (1) 123kV, 550kV BIL, 650A Southern States Cap Switcher with a 150Ω Pre-Insertion Resistor, which has a Primary Fault Interrupting Current of 40kA.
- Install one (1) "CE" 16' Switch Tower (DWG# SSCETW01)
- Install one (1) 115kV, 2000A Vertical Break Disconnect Switch mounted on the "CE" Tower
 - o Install nine (9) porcelain insulators (TR#286) on switch
- Install 120' of 336 ACSR (Linnet) for the jumpers to connect above equipment

<u>115kV Bus</u>

 Install nine (9) 13' lally columns to extend the 115kV transfer bus one bay to the north of the existing cap bank bay

- Install nine (9) porcelain insulators mounted on new lally columns
- Install approx. 230' of 2½" Sch. 40 aluminum to extend the 115kV Transfer Bus and approx. 42' of 1½" Sch. 40 aluminum for the A-Frames.
 - To minimize outages, the bus should include splices in between the existing bus and new bus that will be installed.
- Install approx. 230' of 336 ACSR (Linnet) for bus damping
- Install one (1) yard light

Relay and Settings Work

Capacitor Bank Control:

Install one (1) Capacitor Bank Control Panel. The panel will use a SEL-451.

Install three (3) CVT, 115kv

Install one (1) Junction Box, CVT, Termination, Cable

Install one (1) Neutral PT

Install one (1) Neutral PT Junction Box, Termination, Cable Settings will need to be derived for one capacitor bank control panel consisting of one SEL 451 relay.

Control House Equipment: Upgrade RTU - Status cards & Control cards Install one (1) Orion . One Lot of Control Cable

Contingency – Line traps may be need for this substation – Transfer Trip Comm. to GGN via Baxter Wilson

Communications and SCADA Work

This RTU will be upgraded to MEII/8979 this year (Mike Hendrix is doing this project). Sufficient capacity for a typical capacitor bank addition exists.

4.12 Item 12 - Fayette 115kV Substation: Split the existing 32.4MVAR bank into two (2) 21.6MVAR Capacitor Banks

Site Work

The substation site is large enough to accommodate the new capacitor bank; however, there is a substantial change in elevation of approximately 10 ft inside of the fenced in area. Therefore, although there is significant site work required, no fence lines will need to be removed. The following materials are required to complete the site work:

1000 cu yds of fill dirt 200 cu yds of cut 1 acre of seed and mulch

Foundation Work

The following foundations will need to be installed totaling 31 cu yards of concrete:

One (1) 3 phase capacitor bank foundation

One (1) 115kV Cap switcher foundation

Nine (9) 115kV Low elevation bus support foundations

One (1) 115kV Low elevation switch support foundation

Three (3) 115kV Tubular CVT support foundations

Install approximately 1600 ft of grounding to expand the station Install approximately 4190 ft of conduit.

Install two (2) Pull boxes

Steel and Electrical Work

Existing Capacitor Bank Bay

- The existing bank is a General Electric Fuseless 32.4MVAR bank with a rated voltage of 118.47kV. Each can is rated about 600kVAR. It has three (3) parallel groups with six (6) cans each, a total of 54 cans.
 - 600kVAR * 6(cans) * 3(parallel) * 3(phases) = 32.4MVAR
- So we will remove one (1) series in parallel group (6 cans) per phase to get the desired 21.6MVAR, leaving a total of 36 cans.
 o 600kVAR * 6(cans) * 2(parallel) * 3(phases) = 21.6MVAR

New 21.6MVAR Capacitor Bank Bay

- Install one (1) Shunt, Fuseless, 115kV, 21.6MVAR Capacitor Bank connected ungrounded wye. This bank will have a rated voltage of 118.47kV. It will consist of six (6) cans in each series section (each capacitor has six (6) internal sections), and two (2) series in parallel per phase, which is a total of 36 series sections per string. Each capacitor unit is rated 11.4kV, 600kVAR per can.
 - Install one (1) 69kV Neutral PT and junction box (both ordered by relay designer) which will be mounted on the capacitor bank.
- Install three (3) CVT Support Structures
- Install three (3) CVTs (ordered by relay designer) in between the vertical break switch and the cap switcher. They will be mounted on CVT Support Structures
- Install one (1) 123kV, 550kV BIL, 650A Southern States Cap Switcher with a 150Ω Pre-Insertion Resistor, which has a Primary Fault Interrupting Current of 40kA.
- Install one (1) "ČE" 16' Switch Tower (DWG# SSCETW01)
- Install one (1) 115kV, 2000A Vertical Break Disconnect Switch with a Motor Operator mounted on the "CE" Tower
 - Install nine (9) porcelain insulators (TR#286) on switch

 Install 120' of 336 ACSR (Linnet) for the jumpers to connect above equipment

<u>115kV Bus</u>

- Install nine (9) 13' lally columns to extend the 115kV Operating bus to the south west
 - Install nine (9) porcelain insulators mounted on new lally columns
- Install approx. 230' of 2½" Sch. 40 aluminum to extend the 115kV Operating Bus and approx. 42' of 1½" Sch. 40 aluminum for the A-Frames
 - To minimize outages, the bus should include splices in between the existing bus and new bus that will be installed.
- Install approx. 230' of 336 ACSR (Linnet) for bus damping
- Install one (1) yard light

Relay and Settings Work

Capacitor Bank Control:

Install one (1) 48VDC OUTDOOR Capacitor Bank Control Panel. The panel will use a SEL-451.

Install three (3) CVT, 115kv

Install one (1) Junction Box, CVT, Termination, Cable

Install one (1) Neutral PT

Install one (1) Neutral PT Junction Box, Termination, Cable Settings will need to be derived for one capacitor bank control panel consisting of one SEL 451 relay.

Control House Equipment:

Upgrade RTU - Status cards & Control cards One Lot of Control Cable

Communications and SCADA Work

This RTU will be upgraded to MEII/8979 this year (Mike Hendrix is doing this project). Sufficient capacity for a typical capacitor bank addition exists.

COST

The ICT has reviewed and determined whether each required upgrade will be considered a Base Plan Upgrade or a Supplemental Upgrade. For more information on cost responsibility for Base Plan and Supplemental Upgrades, see Attachment T to Entergy's OATT.

The costs shown in the table include overheads and AFUDC, but do not include tax gross up. Entergy incurs a tax liability proportional to the amount of customer contributions. In addition to proposed project costs, the customer may be charged a "Tax gross-up" (TGU) at applicable rates. Rates are subject to change. TGU is not included in any of the estimates.

Project/Station Description	Base Plan	Supplemental	Total Project	Reference
Rolling Fork 115kV Substation		\$652,418.00	\$652,418.00	4.1
Yazoo City Municipal 115kV Sub.		\$617,916.00	\$617,916.00	4.2
Carthage 115kV Substation		\$844,708.00	\$844,708.00	4.3
Tylertown 115kV Substation		\$900,297.00	\$900,297.00	4.4
Magee 115kV Substation		\$656,843.00	\$656,843.00	4.5
McComb 115kV Substation		\$75,970.00	\$75,970.00	4.6
Senatobia 115kV Substation		\$1,023,537.00	\$1,023,537.00	4.7
Plum Point 115kV Substation		\$914,650.00	\$914,650.00	4.8
Hernando 115kV Substation		\$1,112,844.00	\$1,112,844.00	4.9
Hollandale 115kV Substation		\$1,121,269.00	\$1,121,269.00	4.10
Port Gibson 115kV Substation		\$940,923.00	\$940,923.00	4.11
Fayette 115kV Substation		\$1,034,502.00	\$1,034,502.00	4.12
Grand Totals		\$9,895,877.00	\$9,895,877.00	

Cost Analysis

SCHEDULE

A detailed schedule will be prepared subsequent to customer approval to proceed with the project. Based on the Task duration schedules listed below, the overall project inservice date is projected to be **March 1, 2012.** *Note: see General Assumption in Section 3.* The projects listed in "RED" below are presently being constructed; the projects in "Black" have estimated dates with schedules subject to change.

	Proposed Construction	Proposed ISD	
Task Name	Start Date	(Preliminary, unbaseline)	
Item 8 Plum Point 115kV Substation	August 16,2010	February 07, 2011	
Item 9 Hernando 115kV Substation	Sept. 13, 2010	February 28, 2011	
Item 7 Senatobia 115kV Substation	October 18,2010	March 21,2011	
Item 10 Hollandale 115kV			
Substation	November 15,,2010	April 11,2011	
Rolling Fork 115kV Substation	January 24, 2011	April 07,2011	
Yazoo City Municipal 115kV Sub.	February 21 ,2011	May 23,2011	
Carthage 115kV Substation	February 07, 2011	June 13,2011	
Tylertown 115kV Substation	March 07,2011	October 14,2011	
Item 12 Fayette 115kV Substation	April 18,2011	November 07,2011	
Item 11 Port Gibson 115kV			
Substation	May 31, 2011	November 30, 2011	
McComb 115kV Substation	August 22, 2011	January 11, 2011	
Magee 115kV Substation	August 22, 2011	December 28, 2011	

Notes to Duration Schedules:

- All construction work requiring outages will be performed during acceptable periods of system load flow, which most often is the off-peak load season. Line outages will be discussed with the SOC and TOC and the assumption is made that line outages will be executed as planned. However, last minute denial of outages by the SOC/TOC along with resulting schedule delay is possible.
- Substation construction will be coordinated with the transmission line outages when possible.
- Construction resources are available when required.
- Transmission Line and Substation projects will begin subsequent to Definition phase Project Execution Plan.
- In Service Dates are based on a <u>preliminary, non-constrained (unbaselined)</u> <u>project schedules</u>, and state significant schedule assumptions, such as timing of funding authorization(s), outage approvals, ROW/permitting, etc.
- This schedule does not account for adverse weather conditions.

• Schedule durations are high level estimates at this time. A detailed schedule will be prepared upon project approval.

RISK ASSESSMENT

Identify risk events that may impact cost and/or schedule during execution of the project.

Risk	Comment	Impact
Underground site issues (Pipelines, wells, containments)	Unknown underground factors will add mitigation costs and may impact schedule	***
Substation Site will require minimal site work	Site may be in flood plain, wetlands, Soil Contamination	**
Material transportation could affect cost/schedule	Large transformers(other equipment) may require special transport to substation site	**
Material costs steel & Equipment	Rising steel, copper, fuel and other market conditions could greatly affect estimated cost.	****
Storm-water plan implementation	Best guess on SWPPP creation, implementation and monitoring can vary greatly dependant on outcome of environmental study.	**
Weather & Equipment Lead Times (Transformer, Poles)	Unexpected delays on material lead times, unusually inclement weather will impact schedule but might impact AFUDC costs as well.	**
Wetland mitigation	Undetermined until environmental analysis is complete.	***
Outages may not be available	Preliminary schedule only considers general outage constraints. Specific project schedule may be delayed by days, weeks or months dependant on system conditions. Delays of months = increased project costs.	**
Scope based on design assumptions which may change	Varied impact on cost and schedule.	***

*-low impact to cost, ** - moderate impact to cost, ***- high impact to cost, **** - very high impact to cost.

CONFIRMED RESERVATIONS

The following modifications were made to the base cases to reflect the latest information available:

- Confirmed firm transmission reservations were modeled.
- Approved transmission reliability upgrades for 2009 2011 were included in the base case. These upgrades can be found at Entergy's OASIS web page, http://oasis.e-terrasolutions.com/OASIS/EES, under ICT Planning Studies and Related Documents.

Prior generator interconnection requests that were included in this study:

PID	Substation	MW	In-Service Date
PID 211	Lewis Creek	570	6/1/2011
PID 216	Wilton 230kV	251	1/1/2010
PID 221	Wolf Creek	875	In-Service
PID 222	Ninemile	570	10/1/2012
PID 223	PID-223 Tap	125	10/1/2010
PID 224	PID-224 Tap	100	12/1/2009
PID 225	Big Cajun 2 Unit 3	13	7/31/2009

Prior transmission service requests that were included in this study:

OASIS #	PSE	MW	Begin	End
1604055	Westar Energy Gen & Mktg	15	6/1/2010	6/1/2015
1615068	NRG Power Marketing	52	1/1/2010	1/1/2011

Pre-888 Transactions

See the following hyperlink for a complete listing of all Pre-888 transactions.

http://oasis.e-terrasolutions.com/documents/EES/Pre-Order888Transactions.xls


ATTACHMENTS

A. Table of Acronyms


ACSR	Aluminum Conductor Steel Reinforced
ACSS	Aluminum Conductor Steel Supported
ADEQ	Arkansas Department of Environmental Quality
AFUDC	Allowance for Funds Used During Construction
ATC	Available Transfer Capability
EES	Entergy Control Area
EHV	Extra-High Voltage
ICT	Independent Coordinator of Transmission
kV	Kilo-Volt
МСМ	(M) Thousand Circular Mils
MVA	Mega-Volt Amp
MW	Mega-Watt
NPDES	National Pollution Discharge Elimination System
NOI	Notice of Intent
OASIS	Online Access and Same-time Information System
OATT	Open Access Transmission Tariff
OG&E	Oklahoma Gas & Electric
POD	Point of Delivery
POR	Point of Receipt
SES	Steam Electric Station
SOC	System Operations Center
SHPO	Arkansas State Historic Preservation Office
SHV	Super High Voltage
SW	Switch Station
SWEPCO	Southwest Electric Power Company
ТОС	Transmission Operations Center
WMUC	City of West Memphis Control Area


B. Scope Summary Diagram / Area Map


2010 - 2012 Capacitor Bank Projects Location map Supporting PID 226 and GGU





C. One Line Drawings


























D. Duration Schedule

ndgulf Uprate PID 226					As of Feb-07-10
D EMOC WO / EJO Addivity Name Number	Original Start Duration	Finish	EMCC Target Start	EMCC Target Finish	2010 2010 2011 2012 ONDJFMAMJJJJAASIONDJFMAMJJJJAASONDJFMAMJJJJAASIO
randguif Uprate PID 228	610d Nov-23-09 A	Jun-13-12	Nov-23-09	Apr-21-10	V. Jun 1312;0
Scope Definition Template wFront End Loading	87d Nov-23-09 A	May-18-10	Nov-23-09	Apr-21-10	Wak-18-18, Scope Definition Tempiste will root Engl Lewiting
DEFINITION	87d Nov-23-09 A	Mey-18-10	Nov-23-09	Apr-21-10	W Me-14-10 DEFINITION
Site Visit	51d Dec-02-09 A	Feb-12-10	Dec-02-09	Jan-18-10	9
Front End Loading	71d Feb-08-10	May-17-10	Dec-02-09	Mar-15-10	May-17-10, Feart Eng Loading
Issue Project Execution Plan	66d Nov-23-09 A	Apr-19-10	Nov-23-09	Mar-23-10	Adv-19-10; indue ProjectExecution Pitch
Obtain Project Funding Approval	15d Apr-20-10	May-10-10	Mar-23-10	Apr-13-10	May 10 10 Ottain Project Funding Approval
Beseline Schedule	9d May-06-10	May-18-10	Apr-08-10	Apr-21-10	May-18-10, Baseline Schedule
Plum Point Substation: Add Cepacitor Bank	277d May-28-10	Jun 29-11			7 Jon-20-15, Plure Point Substation: Add Gapacity Ban
DESIGN	181d May-28-10	Feb-14-11			Feb 14-15 DESIGN
Substation Design	108d May-28-10	Oct-27-10			Cit-21-10, Sutstation Design
Relay Design	74d Sep-01-10	Dec-16-10			Dep-16-10 Reiny Depign
Perform Work Order Maintenance	10d Oct-28-10	Nov-10-10			10 Nov 1010 Petron Viori Order Mantenance
Material Procurement	137d Jul-29-10	Feb-14-11			Fel-14-11, Material Produrement
CONSTRUCTION	120d Aug-16-10	Feb-07-11			
As-Built Documents	121d Oct-11-10	Apr-04-11			Apr-p4-11, As-Built Depundent
CLOSEOUT	101d Feb-08-11	Jun-29-11			Mului Jen-29-13, CLOBEDUT
Hernando Substation: Split Cepecitor Bank	273d Jun-23-10	Jul-21-11			V Jul 21 11 Hernando Butenetore Split Capacitor Se
DESIGN	162d Jun-23-10	Feb-14-11			Fel-14-11 DESIGN
Substation Design	89d Jun-23-10	Oct-27-10			The second
Relay Design	88d Sep-01-10	Jan-10-11			Jan-10-11, Relay Design
Perform Work Order Maintenance	10d Oct-28-10	Nov-10-10			107 Nov 10:10 Petforth Work Order Mattebante
Material Procurement	117d Aug-28-10	Feb-14-11			Fel-14-11, Meterlei Procurement
CONSTRUCTION	116d Sep-13-10	Feb-28-11			Fib-18-11, CONSTRUCTION
As-Built Documents	116d Nov-08-10	Apr-25-11			Apr-25-11, Ap-Bailt Documents
CLOSEOUT	101d Mer-01-11	Jul-21-11			Jul 21 11, CLOSEOUT
Senatobia Substation: Add Capacitor Bank	282d Jul-29-10	Aug-10-11			V Aug 10 11 Sehatabia Substation: Add Capacitor
DESIGN	137d Jul-29-10	Feb-14-11			Feb-14-15 DESIGN
Substation Design	64d Jul-29-10	Oct-27-10			Turring Off-27-10, Substation Design
Relay Design	108d Aug-25-10	Jen-31-11			Caracterization and Annual State Sta
Perform Work Order Maintenance	10d Oct 28 10	Nov-10-10			10 Kov 10-10, Pelforh Work Orber Maihtehanbe
Material Procurement	93d Sep-30-10	Feb-14-11			Fels 14-11, Material Procurement
CONSTRUCTION	108d Oct-18-10	Mar-21-11			The second secon
As-Built Documents	108d Dec-13-10	May-13-11			Terrer Wee-1511 AsBalt Doctmetts
CLOSEOUT	100d Mar-22-11	Aug-10-11			televent in the second s
Hollandale Substation: Split Capacitor Bank	258d Aug-25-10	Aug-31-11			Alga B1-11, Hollandale Suthtation Split Capic
DESIGN	158d Aug-25-10	Apr-07-11 Jan-12-11			Apr/07-11_DE\$I08
Substation Design	98d Aug-25-10 64d Nov-15-10	Jan-12-11 Feb-18-11			Ten 12 Fight 1
Relay Design Perform Work Order Maintenance	10d Jan-13-11	Jen-28-11			Total In-12, rener Congo
Material Procurement	111d Oct-28-10	Apr-07-11			Acc27-1 Material Poccement
CONSTRUCTION	101d Nov-15-10	Apr-07-11 Apr-11-11			Reprint Proceeding
As-Built Documents	104d Jan-10-11	Apr-11-11 Jun-08-11			Christian Construction
CLOSEOUT	100d Apr-12-11	Aug-31-11			
Rolling Fork Substation: Add Capacitor Bank	234d Oct-20-10	Sep-22-11			Vige of 1, excession
Remaining Level of Effort Actual Work Cr.			Page 1	of 3	TASK filter: All Activities
Addat work Cr.			-		1

PID 226

DESIGN Substitution Design Relay Design Perform Work Order Maintenance Matheli Procements CONSTRUCTION A-Built Documents CLOSEOUT Year Org Substation: Add Capacitor Bark OBERIN Relay Design Relay Design Relay Design Construction CONSTRUCTION A-Built Documents CLOSEOUT CONSTRUCTION CONSTRUCT	Durition 1174 Oct-00-10 574 Oct-20-50 814 Nav-15-10 104 Jan-15-11 024 Jan-26-10 704 Jan-26-11 024 Jan-26-11 026 May-25-11 026 May-25-11 026 May-15-10 038 Nav-15-10 039 Nav-15-10 039 Nav-15-10 039 Nav-15-10 039 Nav-15-10 030 May-25-11 030 May-26-11	Apr-07-11 Jan-12-11 Mar-15-11 Jan-28-11 Apr-07-11 May-02-11 Jan-27-11 Sep-22-11 Oct-15-11	Target Start Finis	ONDJFMAMJAJASONDJFMAMJJAJASONDJFMA V 1940-111540-040-0 COMPACT Install 1540-040-0 COMPACT Install 1540-040-0 COMPACT Install 1540-040-0 COMPACT Install 1540-040-040-040-040-040-040-040-040-040-	
Risky Dasign Parletim Wash Order Maintenance Maintail Procorament CONSTRUCTION A-Bulk Documents CLOSEOUT Distribution Add Capatitin Bark DEBON Revel Wash Order Maintenance Nature One Status Octores Tractories Construction Parletin Wash Order Maintenance Maintail Procurement Construction Distribution Dation Distribution Statistics Add Capatitin Baris DEBON Bidatation Dation Parletin Wash Order Maintenance Maintiel Procurement Construction	81d Nav-15-10 10d Jan-13-11 02d Nav-34-10 70d Jan-34-11 80d Mar-22-11 80d Mar-25-10 100d Nav-15-10 100d Nav-15-10 100d Pab-17-11 10d Feb-17-11 80d Dac-34-10 80d Feb-27-11 80d Apr-18-11 80d Apr-18-11 80d Apr-18-11	Mar-15-11 Jan-28-11 Apr-07-11 May-02-11 Jun-27-11 Sep-22-11		Construction (Construction)	
Perform Wark Order Maritemance Mariele Provement CONSTRUCTION A-Bult Documents CLOSECUT DESIGN Buckation Design Buckation Design Perform Wark Order Marienance Mariele Provements CLOSECUT Centruge Buckation: Add Cayester Bank DESIGN DESIGN DESIGN Buckation Design Ratey Design DESIGN DESIGN	10d Jan-13-11 82d Nov-24-10 70d Jan-24-11 80d Mar-22-11 100d May-23-11 100d May-15-10 100d Nov-15-10 100d Nov-15-10 75d Dec-14-10 10d Feb-17-11 84d Dec-21-10 86d Feb-21-11 65d Apr-18-11 100d May-24-11	Jan-28-11 Apr-07-11 May-02-11 Jun-27-11 Sep-22-11		THE Jac. 20, 21 Eastern Mide Methodson	+++++
Matisti Procesment Construction As-But Documents C.COSEOU CONSTRUCTION Sector Add Copyoin Bank DEBION DEBION Debion Proferment Debion D	92d Nov-24-10 70d Jan-24-11 90d May-29-11 2314 Nov-15-10 93d Nov-15-10 93d Nov-15-10 10d Feb-21-11 84d Dec-21-10 95d Feb-21-11 95d Apr-18-11 100d May-24-11	Apr-07-11 May-02-11 Jun-27-11 Sep-22-11			+++++
A-B-Bit Documents CLOSEGUT Varies Offy Subattion: Add Capeethir Bark Of Statution: Design Relay Design Relay Design Relay Design Relay Design CONSTRUCTION A-B-Bit Documents CLOSEGUT CUBECUT Cuthings Subattion: Add Capeation: Bark Design Buditation: Design Relay Design Partiery Partiery Partiery Design Partiery	60d Mar-22-11 100d May-05-11 231d Nav-15-10 100d Nav-15-10 63d Nav-15-10 75d Dec-14-10 75d Dec-14-10 10d Feb-21-11 84d Dec-21-10 66d Feb-21-11 100d May-24-11	Jun-27-11 Sep-22-11		Apr207-21, Maderial Plocotement	++++
CLOSECUT Varian City Valuation Add Capeshin Bank DEBIGN Debitidion Design Add Capeshin Bank Debitidion Design Partern Work Order Maintenance Material Procement CLOSECUT Cettage Statistics Add Capeshin Bank Debitidion: Add Capeshin Bank Debitididi	100d May-03-11 231d Nov-15-10 08d Nov-15-10 83d Nov-15-10 75d Dec-14-10 10d Feb-17-11 84d Dec-21-10 86d Feb-21-11 86d Apr-18-11 100d May-24-11	Sep-22-11		May 52-1, DOUSTRUCTION	
Vesic OF Satkafan As Capacitin Bark DEBON Deboto DEBON Deboto Debot Deboto Debot Deb	231d Nov-15-10 100d Nov-15-10 63d Nov-15-10 75d Dec-14-10 10d Feb-17-11 84d Dec-21-10 68d Feb-21-11 65d Apr-18-11 100d May-24-11			The second	
DESION DESION Statution Design Relay Design Relay Design Relay Design Relay Design Relay Descenters CONSTRUCTION A-Built Documents CLOSECUT Contempo Statution: Add Depettor Bank DESidNer Add Depettor Bank DESidNer Maintenance Relay Design	100d Nov-15-10 63d Nov-15-10 75d Dec-14-10 10d Feb-17-11 84d Dec-21-10 66d Feb-21-11 65d Apr-18-11 100d May-24-11			1041311 Xanoo	
Fistery Orasign Fistery Work Order Maintenance Material Procurement CONSTRUCTION A-Built Docurements COCOCCUP CCURSTRUCTION A-Built Docurements CLOSECUT COCCUP Cottinger Substation: Add Capacitor Bank DEBON Bubdiation Design Fistery Dosign Partierne Work Order Maintenance Material Processment	75d Dec-14-10 10d Feb-17-11 84d Dec-21-10 66d Feb-21-11 65d Apr-18-11 100d May-24-11	Apr-21-11		Ad-21-11 DESIGN	
Perform Work Order Martenance Martiel Provement CONSTRUCTION As-Built Documents CLOSEGUT Cuthings Expendion: Add Capacitor Benk DESIGN Builtwardon Design Builtwardon Design Perform Work Order Martenance Martiel Design Perform Work Order Martenance	10d Feb-17-11 84d Dec-21-10 86d Feb-21-11 85d Apr-18-11 100d May-24-11	Feb-16-11		Page 14-14 Add Date 1	
	84d Dec-21-10 66d Feb-21-11 65d Apr-18-11 100d May-24-11	Apr-04-11		The DRCP Apr 94-11, Reidy Clesion	
CONSTRUCTION A-Ball Documents CLOSECUT Cething Extention: Add Capacitor Bank DESION Butwation Design Butwation Design Perform Work Order Maintence Material Procement	66d Feb-21-11 65d Apr-18-11 100d Mey-24-11	Mar-02-11 Apr-21-11		TUP Ner 02-11, Perform Werk Droter Meintergende	++++
CLOSECUT Cettage Substation: Add Capector Bank DESIGN Bubstation Design Relation Design Perform Work Order Maintenance Material Procement	65d Apr-18-11 100d May-24-11	May-23-11		Miy-28-11, doNSTRUCTION	
Certhage Bubetation: Add Capacitor Bank DESION Bubetation Design Relay Design Perform Work Order Meintenance Material Procement		Jul-19-11		To the UP Jul 1911 As Bult Deciments	
DESION Substation Design Relay Design Perform Work Creder Maintenance Mathelia Processment		Od-13-11		VIII Od 1311, CLOSE	TUC
Substation Design Relay Design Perform Work Order Maintenance Material Procurement	243d Nov-17-10 122d Nov-17-10	Nov-02-11 May-12-11		Vov-22-11, DefStdpt	ege Substation: Ar
Relay Design Perform Work Order Maintenance Material Procurement	61d Nov-17-10	Feb-16-11		The second	++++
Material Procurement	90d Dec-13-10	Apr-22-11		Ap-22-11, Relay Delige	
	10d Feb-17-11	Mar-02-11		TUP Mar 22-1, Perform Werk Order Maintenince	
	80d Jan-20-11 90d Feb-07-11	May-12-11 Jun-13-11		Met-12-11 Material Productive	++++
As-Built Documents	89d Apr-04-11	Aug-08-11		Trenduling Aug081113A-Suit Decim	
CLOSEOUT	100d Jun-14-11	Nov-02-11		The second secon	
Tylertown Substation: Add Capacitor Bank	314d Dec-14-10	Mar-13-12			at 13 12 Tylefow
DESIGN Substation Design	191d Dec-14-10 156d Dec-14-10	Sep-15-11 Jul-27-11		V Sep-14-15 DESEN	++++
Relay Design	70d May-23-11	Aug-30-11		Alg-So-11, Serveron Center Alg-So-11, Serveron Center	+++++
Perform Work Order Maintenance	10d Jul-28-11	Aug-10-11		The second	
Material Procurement	148d Feb-17-11	Sep-15-11		Seb-15-11, Métedal Pr	ocurement
CONSTRUCTION As-Built Documents	157d Mer-07-11 158d Mey-02-11	Od-14-11 Dec-13-11		0041411,00012	RUCTION
CLOSEOUT	102d Oct-17-11	Mar 13-12			a) 13 12 CL08E
Feyette Substation: Split Capacitor Bank	300d Jan-27-11	Apr-03-12			Apr-03-12, Fayed
DESIGN	187d Jan-27-11	Oct-20-11			
Substation Design	127d Jen-27-11 78d Jun-01-11	Jul-27-11		Line and the second sec	11111
Reley Design Perform Work Order Maintenance	76d Jun-01-11 10d Jul-28-11	Sep-19-11 Aug-10-11		The second secon	gi Irder Mabilebarde
Material Procurement	163d Mar-03-11	Oct-20-11		Cd-20-11 Materia	Procurement
CONSTRUCTION	143d Apr-18-11	Nov-07-11		kova7-t1,cON	STRUCTION
As-Built Documents CLOSEOUT	143d Jun-14-11	Jan-08-12			
Port Gibeon Substation: Split Capacitor Bank	101d Nov-08-11 288d Mar-10-11	Apr-03-12 Apr-24-12			April 12, club
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work M	-		Page 2 of 3) Primavera Sy
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work M			Page 2010) Primavera Sy
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work • • M adgulf Uprate PID 226	Crignal Start Duration	Pinish	TENICC	As of Feb-07-10	2012
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work • • M adgulf Uprate PID 226	Original Start Duration 156d Mar-10-11	Pinah Oct-20-11	TENICC	с терен As of Feb-07-10 С терен Ла от разка и страна и с	
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work + M Indgulf Uprate PID 226 EMOC WO 7E30 Activity Name Namber DESION Substration Design	Duration 158d Mar-10-11 98d Mar-10-11	Oct-20-11 Jul-27-11	TENICC	C Teger 2010 2011 2011 2011 2011 2011 2011 201	2012 M A M J Juli SON
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work MI Actual Work MI Actua	Duration 158d Mar-10-11 98d Mar-10-11 91d Jun-01-11	Oct-20-11 Jul-27-11 Oct-10-11	TENICC	C 10001 As of Feb-07-10 C 10001 C 100001 C 10001 C 1	2012 V A M J Jul SON Son Son Son
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work Mu adguilf Uprate PID 226 EMOC WO 7E30 Activity Name Namber DESION Substation Design Relay Design Relay Design Relay Design	Duration 158d Mar-10-11 98d Mar-10-11 91d Jun-01-11 10d Jul-28-11	Oct-20-11 Jul-27-11 Oct-10-11 Aug-10-11	TENICC	As of Feb-07-10	2012 V A M J Jul SON Son Son Son
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work MI Actual Work MI Actua	Duration 158d Mar-10-11 98d Mar-10-11 91d Jun-01-11	Oct-20-11 Jul-27-11 Oct-10-11	TENICC	As of Feb-07-10	2012 M A M J Jul 2014 den Design f Onler Matter
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work ML Actual Vorte PID 226 Remaining Level of Effort Remaining Work ML Actual Vorte PID 226 Remaining Level of Effort Remaining Work Actual Work Actua	Duration 158d Mar-10-11 98d Mar-10-11 91d Jun-01-11 10d Jul-28-11 113d May-12-11 129d May-31-11 130d Jul-25-11	Oct-20-11 Jul-27-11 Oct-10-11 Aug-10-11 Oct-20-11 Nov-30-11 Jan-27-12	TENICC	C TAIL C C C C C C C C C C C C C C C C C C C	2012 A M J Jul 2014 Design Cesign cal Roducehead Doi stikutee
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work • • M adgulf Uprate PID 226 EMCC W07ED0 Activity Name Namber DESIGN Subsidian Design Resp Desig	Duration 158d Mar-10-11 98d Mar-10-11 91d Jun-01-11 10d Jul-28-11 113d May-12-11 129d May-31-11 130d Jul-28-11 100d Dec-01-11	Oct-20-11 Jul-27-11 Oct-10-11 Aug-10-11 Oct-20-11 Nov-30-11 Jan-27-12 Apr-24-12	TENICC		2012 A A M J Jul RN Design Cover Matter dal Rodurenest Dorsk Ruppo 27-12, A=Gatto Ad-29-12,
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work ML. Actual Level of Effort Remaining Work ML. Actual Level of Effort Remaining Work ML. Actual Level of Effort Remaining Work ML. Construction Relation Design Relation Design Relation Design Relation Design Relation Construction CONSTRUCTI	Duriélon 158d Mar-10-11 98d Mar-10-11 91d Jun-01-11 10d Juh-28-11 113d May-12-11 120d May-31-11 120d Juh-25-11 100d Dec-01-11 285d May-18-11	Oct-20-11 Jul-27-11 Oct-10-11 Aug-10-11 Oct-20-11 Nov-30-11 Jun-27-12 Apr-24-12 Jun-04-12	TENICC	As of Feb-07-10	2012 Al A M J Jul DEN Design Design Al Design Martices al Design Al Design Martices al Design Al
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work • • M adgulf Uprate PID 226 EMCC W07ED0 Activity Name Namber DESIGN Subsidian Design Resp Desig	Duration 158d Mar-10-11 98d Mar-10-11 91d Jun-01-11 10d Jul-28-11 113d May-12-11 129d May-31-11 130d Jul-28-11 100d Dec-01-11	Oct-20-11 Jul-27-11 Oct-10-11 Aug-10-11 Oct-20-11 Nov-30-11 Jan-27-12 Apr-24-12	TENICC	C TAIL C C C C C C C C C C C C C C C C C C C	2012 A M J Jul 2014 In Design 10 On ar Marteel and Roduetned 2015/25/20/25/25 2015/25/20/25 44-28-15 44-28-15 44-28-15 4, 0685/01
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work Mi Actual Level of Effort Remaining Work Mi Actual Level of Effort Remaining Work Mi Actual Violation Actual PLD Construction Actual Actua	Duriéton 1584 Mar-10-11 984 Mar-10-11 914 Jun-01-11 104 Jul-28-11 1134 May-31-11 1204 May-31-11 1004 Jul-25-11 1004 Jul-25-11 1044 May-18-11 914 May-18-11 914 May-18-11	Oct-20-11 Jul-27-11 Oct-10-11 Aug-10-11 Oct-20-11 Nev-30-11 Jan-27-12 Apr-24-12 Jun-04-12 Dec-27-11 Sep-28-11 Oct-25-11	TENICC	As of Feb-07-10	2012 A M J Jul 2014 In Design 10 On ar Marteel and Roduetned 2015/25/20/25/25 2015/25/20/25 44-28-15 44-28-15 44-28-15 4, 0685/01
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work Mi Actual Level of Effort Remaining Work Mi Effort Work Chef Maintenance Material Procurement CLOREFOLT Estorts	Duriéton 1588 Mar-10-11 984 Mar-10-11 914 Jun-01-11 104 Jul-28-11 1134 May-12-11 1204 May-12-11 1004 Dec-01-11 2856 May-18-11 1544 May-18-11 914 May-18-11 104 Sep-27-11	Oct-20-11 Jul-27-11 Oct-10-11 Aug-10-11 Oct-20-11 Nov-30-11 Jen-27-12 Jun-04-12 Dec-27-11 Sep-28-11 Oct-25-11 Oct-25-11	TENICC	As of Feb-07-10	2012 A A M J Jal Jan Design Design Design Design Design Design Tri 1, 49-EM Tri 1, 49-EM
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work M Actual Level of Effort Remaining Work M Actual Violation Remaining	Durition 1564 Mar-10-11 064 Mar-10-11 064 Jau-00-11 064 Jau-00-11 104 Jau-00-11 1034 May-10-11 1034 May-10-11 1034 May-10-11 1034 May-10-11 1034 May-10-11 074 Jau-20-11 1034 May-20-11	Oct-20-11 Jul-27-11 Oct-10-11 Aug-10-11 Oct-20-11 Nev-30-11 Jun-27-12 Apr-34-12 Jun-04-12 Dec-27-11 Sep-26-11 Oct-30-111 Dec-27-11	TENICC		2012 A A M J JJ 201 201 201 201 201 201 201 201
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work Mi Actual Level of Effort Remaining Work Mi Effort Work Chef Maintenance Material Procurement CLOREFOLT Estorts	Duriéton 1588 Mar-10-11 984 Mar-10-11 914 Jun-01-11 104 Jul-28-11 1134 May-12-11 1204 May-12-11 1004 Dec-01-11 2856 May-18-11 1544 May-18-11 914 May-18-11 104 Sep-27-11	Oct-20-11 Jul-27-11 Oct-10-11 Aug-10-11 Oct-20-11 Nov-30-11 Jen-27-12 Jun-04-12 Dec-27-11 Sep-28-11 Oct-25-11 Oct-25-11	TENICC		2012 2014 2014 2014 2014 2015
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work MI Actual View Child Maintenance Material Processment CONSTRUCTION Actual Documents CONSTRUCTION Actual Processment CONSTRUCTION Actual Processment CONSTRUCTION Actual Documents CONSTRUCTION	Durition 1884 Mar-10-11 884 Mar-10-11 884 Mar-10-11 884 Mar-10-11 884 Mar-10-11 1984 May-10-11 1984 May-10-11 1984 May-10-11 1984 May-10-11 1984 May-10-11 1984 May-10-11 1984 May-20-11 884 Aug-20-11 884 Aug-20-11 884 Aug-20-11 884 Aug-20-11 1984 Aug-20-	Oct-20-11 Jul-27-11 Oct-10-11 Aug-10-11 Oct-20-11 Nev-30-11 Jun-04-12 Jun-04-12 Dec-27-11 Jun-04-12 Dec-27-11 Jen-27-11 Jen-27-11 Jen-27-11 Jen-27-11 Jen-27-11 Jen-04-12	TENICC		2012 2014 2014 2014 2014 2015
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work M Actual Level of Effort Remaining Work M Actual Uprate PID 226 EMOC 9907 EXIC Activity Name Refy Design Perform Work Order Maintenance Material Procement CONSTRUCTION Actual Content Maintenance Material Procement CONSTRUCTION Substation Objets Bestorement CONSTRUCTION Substation Objets Bestorement CONSTRUCTION Actual Monte Maintenance Material Procement CONSTRUCTION Actual Conter Maintenance Material Procements CONSTRUCTION Actual Conter Maintenance Material Procements CONSTRUCTION Actual Conter Maintenance Material Procements CONSTRUCTION	Durition 1564 Mar-10-11 564 Mar-10-11 564 Mar-10-11 564 Mar-10-11 564 Mar-10-11 104 Jun-23-11 104 May-31-11 1040 May-10-11 1040 May-10-11 1040 May-10-11 1040 May-10-11 1040 May-10-11 1040 May-20-11 1040 May-2	Oct-20-11 Jul-27-11 Oct-10-11 Aug-10-11 Oct-20-11 Nex-30-11 Jun-04-12 Jun-04-12 Jun-04-12 Jun-04-12 Dec-27-11 Dec-27-11 Dec-27-11 Jun-04-12 Jun-04-12 Jun-04-12 Jun-04-12 Jun-04-12	TENICC	As of Feb-07-10	2012 A A M J Jai 2011 Design Design College Machine College Machine College Machine College Machine College College Machine College Col
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work Actual Very of Effort Remaining Work Actual Very Color Activity Name Namber DESIGN Substation Design Rely Design Perform Work Order Maintenance Material Processment CONSTRUCTION As-Balt Sociements CONSTRUCTION As-Balt Sociements CONSTRUCTION As-Balt Documents CONSTRUCTION Balt Add Procements CONSTRUCTION CONSTRUCTION Balt Documents CONSTRUCTION Balt Documents CONSTRUCTION Balt Add Concerned Balt Add Concerned CONSTRUCTION Balt Add Concerned	Durition 1560 Mar-10-11 960 Mar-10-11 961 Jul-01-11 961 Jul-01-11 961 Jul-01-11 1961 May-16-11 1964 May-16-11 1964 May-16-11 1964 May-16-11 1964 May-16-11 1964 May-16-11 1964 May-16-11 1964 Jul-21-11 1964 Jul-21-11 1964 Jul-21-11 1964 Jul-21-12 2064 Jul-20-11 2054 Jul-20-11	0d-30511 34-27-11 0d-30-11 0d-30-11 0d-30-11 Nev-30-11 Jan-37-12 Jan-34-12 J	TENICC	Control 1000 Control 10000 Control 10000 Control 10000 Control 1000 Control 1000	A M J J A M J J J Dist Dist Dist Dist Dist Dist Dist Dist Dist Dist Dist Dist Dis Dis Dis <
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work M Actual Level of Effort Remaining Work M Actual Uprate PID 226 EMOC 9907 EXIC Activity Name Refy Design Perform Work Order Maintenance Material Procement CONSTRUCTION Actual Content Maintenance Material Procement CONSTRUCTION Substation Objets Bestorement CONSTRUCTION Substation Objets Bestorement CONSTRUCTION Actual Monte Maintenance Material Procement CONSTRUCTION Actual Conter Maintenance Material Procements CONSTRUCTION Actual Conter Maintenance Material Procements CONSTRUCTION Actual Conter Maintenance Material Procements CONSTRUCTION	Durition 1564 Mar-10-11 564 Mar-10-11 564 Mar-10-11 564 Mar-10-11 564 Mar-10-11 104 Jun-23-11 104 May-31-11 1040 May-10-11 1040 May-10-11 1040 May-10-11 1040 May-10-11 1040 May-10-11 1040 May-20-11 1040 May-2	Oct-20-11 Jul-27-11 Oct-10-11 Aug-10-11 Oct-20-11 Nex-30-11 Jun-04-12 Jun-04-12 Jun-04-12 Jun-04-12 Dec-27-11 Dec-27-11 Dec-27-11 Jun-04-12 Jun-04-12 Jun-04-12 Jun-04-12 Jun-04-12	TENICC	Control 1000 Control 10000 Control 10000 Control 10000 Control 1000 Control 1000	A M 3 AU A A M 3 AU A A M 3 AU A A M 3 AU Design Design Au Au Au C C C Au Au <t< td=""></t<>
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work Mill Actual Level of Effort Remaining Work Mill Actual Work Actual	Durition 1568 Marc10-11 968 Marc10-11 961 Jan-10-11 961 Jan-26-11 100 Jan-26-11 100 Jan-26-11 100 Jan-26-11 100 Jan-26-11 100 Jan-26-11 100 Jan-26-11 100 Jan-26-11 100 Jan-26-12 100 Jan-26	0d-30-11 Jul-27-11 Od-10-11 Aug-10-11 Od-30-11 Od-30-11 Jul-27-12 De-37-11 Jul-27-12 De-37-11 Jul-27-12 De-37-11 Jul-27-12 Mar-06-12 Jul-26-12 Jul-26-12 Jul-26-12 Sep-27-11 Sep-27-11 Sep-27-11 Sep-27-11 Sep-27-11 Sep-27-11 Sep-27-11	TENICC	C As of Feb-07-10	2012 (A A M J J J
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work Actual	Durition 1560 Marc1051 1660 Marc1051 1670 Jau-01-11 1671 Jau-01-11 1671 Jau-01-11 1672 Jau-01-11 1672 Jau-01-11 1676 Jau-01-11 1776 Jau-01-11 1777 Jau-01-10 1777 J	04:30-11 Jul-27-11 04:10-11 Aug-10-11 04:30-11 04:30-11 04:30-11 Jun-37-12 Aug-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Nac-36-11 Dec-27-11 Dec-2	TENICC	As of Feb-07-10	2014 A A J J J J J A A J J J J J A C J J J J J J J A C J J J J J J J J J J J J J J J J J J
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work Mill Actual Level of Effort Remaining Work Mill Actual Work Actual Wor	Durition 1568 Marc10-11 968 Marc10-11 961 Jan-10-11 961 Jan-20-11 191 Jan-20-11 1930 Jan-20-11 1930 Jan-20-11 1930 Jan-20-11 1930 Jan-20-11 1930 Jan-20-11 1930 Jan-20-11 1930 Jan-20-11 1936 Jan	Oct-20511 Jul-27-11 Oct-10511 Jul-27-12 Aug-10511 Oct-20511 Jul-27-12 Jul-06-12 Jul-06-12 Jul-06-12 Jul-06-12 Jul-06-12 Jul-06-12 Jul-06-12 Jul-06-12 Mar-06-12 Jul-06-12 Mar-06-12 Jul-06-12 Mar-06-12 Jul-06-12 Mar-06	TENICC	As of Feb-07-10	2012 A (M) J Jac Physical Constraints Con
Remaining Level of Effort Actual Work Cr Actual Level of Effort Remaining Work Actual Vice of Effort Remaining Work Actual Work Crements Construction Constr	Durition 1560 Marc1051 1660 Marc1051 1670 Jau-01-11 1671 Jau-01-11 1671 Jau-01-11 1672 Jau-01-11 1672 Jau-01-11 1676 Jau-01-11 1776 Jau-01-11 1777 Jau-01-10 1777 J	04:30-11 Jul-27-11 04:10-11 Aug-10-11 04:30-11 04:30-11 04:30-11 Jun-37-12 Aug-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Jun-36-12 Nac-36-11 Dec-27-11 Dec-2	TENICC	As of Feb-07-10	2012 (A A M J Jar) (Boston 1 (Constraint) (C

E. Stability Study Report



POWER SYSTEMS DIVISION GRID SYSTEMS CONSULTING

STABILITY ANALYSIS FOR FACILITY STUDY OF PID-226

FINAL REPORT

REPORT NO.: 2009-E3350-R1 **Issued On**: August 19, 2009 **Revised on**: August 27, 2009 **Revised on**: February 19, 2010

Prepared for: Southwest Power Pool, Inc.

ABB Inc. Power Systems Division Grid Systems Consulting 940 Main Campus Drive, Suite 300 Raleigh, NC 27606

Legal Notice

This document, prepared by ABB Inc., is an account of work sponsored by Southwest Power Pool, Inc. (SPP). Neither SPP nor ABB Inc, nor any person or persons acting on behalf of either party: (i) makes any warranty or representation, expressed or implied, with respect to the use of any information contained in this report, or that the use of any information, apparatus, method, or process disclosed in this report may not infringe privately owned rights, or (ii) assumes any liabilities with respect to the use of or for damages resulting from the use of any information, apparatus, method, or process disclosed in this document.



ABB Inc – Grid Systems Consulting

Technical Report

Southwest Power Pool,	No. 2009-E3350	No. 2009-E3350-R1		
Facility Study for PID-226	Date: 8/21/2009	# Pages 45		
Author(s): Trinadh Dwibhashyam	Reviewed by: Amit Kekare	Approved by: Willie Wong		

Executive Summary

Southwest Power Pool, Inc (SPP) at the request of Entergy Services Inc. has commissioned ABB Inc. to perform a stability analysis for Facility study of PID-226, which is a request for 206 MW uprate of existing G. Gulf Unit #1 in the Entergy transmission system.

A system impact study for the PID-226 has previously been completed. The objective of this study was to supplement the stability analysis performed in the system impact study for PID-226 Project. To that end, selected faults at G. Gulf 500 kV substation were simulated and a Critical Clearing Time Analysis was performed at G. Gulf 500 kV substation. The study was performed on 2012 Summer Peak case, provided by SPP/Entergy.

The system was stable following all simulated normally cleared and stuck-breaker faults. No voltage criteria violation was observed following simulated faults.

The Critical Clearing times at G. Gulf 500 kV substations are within the capabilities of the existing protection systems. The smallest CCT at G. Gulf 500 kV substation was 5 + 15 cycles for a fault involving loss of G. Gulf – B. Wilson 500 kV.

Based on the results of stability analysis it can be concluded that proposed PID-226 project does not adversely impact the stability of the Entergy System in the local area. Also, PID-226 does not adversely impact the Critical Clearing time at G. Gulf 500 kV substations. Hence, no transmission reinforcements and/ or upgrades were identified for the interconnection of the PID-226 project.



The results of this analysis are based on available data and assumptions made at the time of conducting this study. If any of the data and/or assumptions made in developing the study model change, the results provided in this report may not apply.

Rev No.	Revision Description	Date	Authored by	Reviewed by	Approved by		
0	Draft Report	8/21/09	Trinadh	A. Kekare	W. Wong		
1	Updated per Entergy comments	8/27/09	Trinadh	A. Kekare	W. Wong		
2	Updated for Ray Braswell 500 kV fault results	02/19/10	Trinadh	A. Kekare	W. Wong		
DISTRIBUTION: Daniel Epperson – Southwest Power Pool, Inc. Brad Finkbeiner – Southwest Power Pool, Inc. Mukund Chander – Entergy Services Inc.							



TABLE OF CONTENTS

1	INTRODUCTION	6
2	STABILITY ANALYSIS	7
2.1	STABILITY ANALYSIS METHODOLOGY	7
2.2	STUDY MODEL DEVELOPMENT	9
2.3	TRANSIENT STABILITY ANALYSIS	12
2.4	CRITICAL CLEARING TIME ANALYSIS	24
3	CONCLUSIONS	27
APPENDIX A	DATA PROVIDED BY CUSTOMER	28
APPENDIX B	LOAD FLOW AND STABILITY DATA IN PSSE FORMAT	43
APPENDIX C	PLOTS FOR STABILITY SIMULATIONS	45



1 INTRODUCTION

Southwest Power Pool, Inc. (SPP) at the request of Entergy Services Inc. has commissioned ABB Inc. to perform a stability analysis for Facility Study of PID-226, which is a request for 206 MW uprate of the existing G. Gulf Unit in the Entergy transmission system.

A system impact study¹ for the PID-226 has previously been completed. The objective of this study was to supplement the stability analysis performed in the system impact study for PID-226 Project. The study was performed on 2012 Summer Peak case, provided by Entergy. Figure 1-1 shows the location of the G. Gulf Unit with proposed 206 MW increase of generation.




Figure 1-1 PID 226 Project location



¹ "Stability Analysis for PID-226 System Impact study", March 30, 2009

2 STABILITY ANALYSIS

2.1 STABILITY ANALYSIS METHODOLOGY

Using Planning Standards approved by NERC, the following stability definition was applied in the Transient Stability Analysis:

"Power system stability is defined as that condition in which the differences of the angular positions of synchronous machine rotors become constant following an aperiodic system disturbance."

Stability analysis was performed using Siemens-PTI's PSS/E[™] dynamics program V30.3.2. Three-phase and single-phase line faults were simulated for the specified duration and synchronous machine rotor angles and wind turbine generator speeds were monitored to check whether synchronism is maintained following fault removal.

Based on the Entergy study criteria, three-phase faults with normal clearing and delayed clearing were simulated.

Stability analysis was performed using the PSS/E dynamics program, which only simulates the positive sequence network. Unbalanced faults involve the positive, negative, and zero sequence networks. For unbalanced faults, the equivalent fault admittance must be inserted in the PSS/E positive sequence model between the faulted bus and ground to simulate the effect of the negative and zero sequence networks. For a single-line-to-ground (SLG) fault, the fault admittance equals the inverse of the sum of the positive, negative and zero sequence Thevenin impedances at the faulted bus. Since PSS/E inherently models the positive sequence fault impedance, the sum of the negative and zero sequence Thevenin impedances needs to be added and entered as the fault impedance at the faulted bus.

For three-phase faults, a fault admittance of –j2E9 is used (essentially infinite admittance or zero impedance). For the single phase stuck breaker faults, the fault admittances considered are mentioned in Table 2-4.

Transient Voltage Criteria

In addition to criteria for the stability of the machines, Entergy has evaluation criteria for the transient voltage dip as follows:

- 3-phase fault or single-line-ground fault with normal clearing resulting in the loss of a single component (generator, transmission circuit or transformer) or a loss of a single component without fault: Not to exceed 20% for more than 20 cycles at any bus Not to exceed 25% at any load bus Not to exceed 30% at any non-load bus
- 3-phase faults with normal clearing resulting in the loss of two or more components (generator, transmission circuit or transformer), and SLG fault with delayed clearing resulting in the loss of one or more components:



Not to exceed 20% for more than 40 cycles at any bus Not to exceed 30% at any bus

The duration of the transient voltage dip excludes the duration of the fault. The transient voltage dip criteria will not be applied to three-phase faults followed by stuck breaker conditions unless the determined impact is extremely widespread.

The voltages at all local buses (above 115 kV) were monitored during each of the fault cases as appropriate.

As there is no specific voltage dip criteria for three-phase stuck breaker faults, the results of these faults were compared with the most stringent voltage dip criteria of - not to exceed 20 % for more than 20 cycles.

Critical Clearing Time (CCT) Analysis

An evaluation of the critical clearing times was carried out for faults on lines and transformers in the G. Gulf 500 kV substation

Critical Clearing Time assessment was performed on 2012 summer peak system conditions.

Critical Clearing Time (CCT) was calculated for a three-phase stuck-breaker fault on each branch connected to G. Gulf 500 kV substation. CCT is defined as the longest fault clearing time for which stability is maintained.

Independent pole operation (IPO) was assumed for breakers in both switchyards, with breaker failure occurring on only a single phase. This results in a three-phase fault becoming a single-phase fault at the normal clearing time. The single phase fault is then cleared by backup protection.

The Normal Clearing Time was kept equal to the normal value (5 cycles on 500 kV and 6 cycles on 230 kV) and the backup clearing time was varied to find the CCT. All machines in the Entergy system were monitored for stability.



2.2 STUDY MODEL DEVELOPMENT

The study model consists of power flow cases and dynamics databases, developed as follows.

Power Flow Case

A Powerflow case "EN12S08_Final_U2_With Upgrades_unconv.sav" representing the 2012 Summer Peak conditions was provided by SPP/ Entergy.

Two prior-queued projects, PID-223 and PID-224, were added to the base case. Thus a pre-project powerflow case was established and named as 'PRE-PID-226.sav'.

The proposed PID-226 project is a 206 MW uprate at G. Gulf Unit. The additional 206 MW was dispatched against the White Bluff Unit #1. Table 2-1_summarizes the dispatch. Thus a post-project power flow case with PID-226 was established and named as 'POST-PID-226.sav'.

System condition	MW	Point of Interconnection	Sink					
2012 Summer Peak	206	G. Gulf (#336821)	White Bluff Unit 1 (#337652)					

Table 2-1 PID-226 project details

Figure 2-1 shows the PSS/E one-line diagram for the local area WITH the PID-226 project, for 2012 Summer Peak system conditions.

Stability Database

A base case stability database was provided by SPP/Entergy in a PSSE *.dyr file format ('red11S_newnum.dyr').

To create a dynamic database (a snapshot file) for PRE-PID-226 powerflow case, stability data for PID-223 and PID-224 and the dynamic data in 'dystop.dyr' was appended to the base case stability database.

After the proposed uprate of the G. Gulf unit the total MW output of the plant will be 1544 MW, higher than the existing maximum limit (0.90 p.u. on 1600 MVA) on the Governor. For the stability analysis purpose, to avoid the initial condition errors, the limit was changed from 0.90 p.u to 0.97 p.u. on 1600 MVA base. Given the large system under consideration impact of such assumption will not be significant. The pre-project stability database was updated to create dynamic database for Post-PID-226 powerflow case.

The data provided at the Interconnection Request for PID-226 is included in Appendix A. The PSS/E power flow and stability data for PID-226, used for this study, are included in Appendix B.






Figure 2-1 One-line Diagram of the local area without PID-226 (2012 Summer Peak)




Figure 2-2 One-line Diagram of the local area with PID-226 (2012 Summer Peak)

2.3 TRANSIENT STABILITY ANALYSIS

Stability simulations were run to examine the transient behavior of the G. Gulf Unit and impact of the proposed uprate on the Entergy system. Stability analysis was performed using the following procedure. First, three-phase faults with normal clearing were simulated. Next, the three-phase stuck breaker (IPO: 3PH-1PH) faults were simulated. The fault clearing times used for the simulations are given inTable 2-2.

Table 2-2. Fault Cleaning Times						
Contingency at kV level	Normal Clearing	Delayed Clearing				
500	5 cycles	5+9 cycles				

The breaker failure scenario was simulated with the following sequence of events:

1) At the normal clearing time for the primary breakers, the faulted line is tripped at the far end from the fault by normal breaker opening.

2) The fault remains in place for Three-phase stuck-breaker (IPO: 3PH-1PH) faults. The fault admittances is changed to Thevenin equivalent admittance of single phase faults.

3) The fault is then cleared by back-up clearing. If the system was found to be unstable, then the fault was repeated without the proposed PID-226 project.

All line trips are assumed to be permanent (i.e. no high speed re-closure).

Table 2-3 and Table 2-4 list all the fault cases that were simulated in this study.

Fifteen (15) three phase normally cleared and twenty seven (27) three-phase stuck breaker converted into single-line-to-ground fault (following Independent Pole Operation of breakers) were simulated.

For all cases analyzed, the initial disturbance was applied at t = 0.1 seconds. The breaker clearing was applied at the appropriate time following this fault inception.



CASE	LOCATION	TYPE	CLEARING TIME (cycles)	BREAKER TRIP #	TRIPPED FACILITIES
FAULT-1	G. Gulf - B. Wilson 500 kV	3 PH	5	J5224, J5216, J2240, J2244	G. Gulf - B. Wilson 500 kV
FAULT-2	G. Gulf - Franklin 500 kV	3 PH	5	J2425, J2420, J5248, J5240	G. Gulf - Franklin 500 kV
FAULT-3	B. Wilson - Perryville 500 kV	3 PH	5	R7372,R9872, J2233, J2218	B. Wilson - Perryville 500 kV
FAULT-4	B. Wilson - Ray Braswell 500 kV	3 PH	5	J4928, J4920, J2230, J2233	B. Wilson - Ray Braswell 500 kV
FAULT-5	B. Wilson 500/115 kV transformer #1	3 PH	5	J2214, J2222,	B. Wilson 500/115 kV transformer #1
FAULT-6	Ray Braswell - Franklin 500 kV	3 PH	5	J2404, J2408, J4908, J4904	Ray Braswell - Franklin 500 kV
FAULT-7	Ray Braswell - Lakeover 500 kV	3 PH	5	J4928,J4908, J9218, J9234	Ray Braswell - Lakeover 500 kV
FAULT-8	Ray Braswell - B. Wilson 500 kV	3 PH	5	J4928, J4920, J2230, J2233	Ray Braswell - B. Wilson 500 kV
FAULT-9	Ray Braswell 500/ 115 kV Transformer #1	3 PH	5	J4904, J4917	Ray Braswell 500/ 115 kV Transformer #1
FAULT-10	Ray Braswell 500/ 230 kV Transformer #1	3 PH	5	J4917, J4920	Ray Braswell 500/ 230 kV Transformer #1
FAULT-11	Franklin - McKinight 500 kV	3 PH	5	BRK#21105, BRK#21110, J2416,2412	Franklin - McKinight 500 kV
FAULT-12	Franklin - Bogal USA - Adams Creek 500 kV	3 PH	5	S4402, S4405, J2416, J2420	Franklin - Bogal USA - Adams Creek 500 kV
FAULT-13	Franklin - Ray Braswell 500 kV	3 PH	5	J2404, J2408, J4908, J4904	Franklin - Ray Braswell 500 kV
FAULT-14	Franklin - G. Gulf 500 kv	3 PH	5	J2425, J2420, J5248, J5240	Franklin - G. Gulf 500 kv
FAULT-15	Franklin 500/115 kV transformer #1	3 PH	5	J2425, J2404	Franklin 500/115 kV transformer #1


Table 2-3 List of 3 Phase faults simulated for stability analysis

CASE	LOCATION	TYPE	CLEARING (cycle	-	SLG FAULT	STUCK BREAKER	PRIMARY BREAKER	SECONDARY BREAKER	TRIPPED FACILITIES
			PRIMARY	Back- up	(MVA)	#	TRIP #	TRIP	
FAULT-1a	G. Gulf - B. Wilson 500 kV	3 PH/SLG	5	9	640.02- j8505.34	J5224	J5216, J2240, J2244	J5208, J5236, J5248	G. Gulf - B. Wilson 500 kV
FAULT-2b	G. Gulf - Franklin 500 kV	3 PH/SLG	5	9	640.02- j8505.34	J5248	J2425, J2420, J5240	J5208, J5236, J5224	G. Gulf - Franklin 500 kV
FAULT-3a	B. Wilson - Perryville 500 kV	3 PH/SLG	5	9	779.96- j8641.41	J2233	R7372,R9872, J2218	J2230, J4928, J4920	B. Wilson - Perryville 500 kV; B. wilson Ray Braswell 500 kV
FAULT-3b	B. Wilson - Perryville 500 kV	3 PH/SLG	5	9	779.96- j8641.41	J2218	R7372,R9872, J2233	J2214, J2252, J2225	B. Wilson - Perryville 500 kV; B. Wilson 500/115 kV transformer#1
FAULT-4a	B. Wilson - Ray Braswell 500 kV	3 PH/SLG	5	9	779.96- j8641.41	J2233	J4928, J4920, J2230	R7372,R9872, J2218	B. Wilson - Ray Braswell 500 kV; B. Wilson - Perryville 500 kV
FAULT-4b	B. Wilson - Ray Braswell 500 kV	3 PH/SLG	5	9	779.96- j8641.41	J2230	J4928, J4920, J2233	J2240, J2236, J2222	B. Wilson - Ray Braswell 500 kV
FAULT-5a	B. Wilson 500/115 kV transformer #1	3 PH/SLG	5	9	779.96- j8641.41	J2214	J2222	J2218, J2252, J2225	B. Wilson 500/115 kV transformer #1
FAULT-6a	Ray Braswell – Franklin 500 kV	3 PH/SLG	5	9	765.3- j6686.74	J4908	J2404, J2408, J4904	J4928, J9218, J9234	Ray Braswell - Franklin 500 kV; Ray Braswell - Lakeover 500 kV
FAULT-6b	Ray Braswell Franklin 500 kV	3 PH/SLG	5	9	765.3- j6686.7 4	J4904	J2404, J2408, J4908	J4917	Ray Braswell - Franklin 500 Kv; Ray Braswell 500/115 kV transformer #1
FAULT-7a	Ray Braswell - Lakeover 500 kV	3 PH/SLG	5	9	765.3- j6686.74	J4928	J4908, J9218, J9234	J2230, J2233, J4920	Ray Braswell – Lakeover 500 kV; Ray Braswell – B. Wilson 500 kV
FAULT-7b	Ray Braswell - Lakeover 500 kV	3 PH/SLG	5	9	765.3- j6686.74	J4908	J4928, J9218, J9234	J4904, J2404, J2408	Ray Braswell - Lakeover 500 kV, Ray Braswell - Franklin 500 kV
FAULT-8a	Ray Braswell – B. Wilson 500 kV	3 PH/SLG	5	9	765.3- j6686.74	J4928	J4920, J2230, J2233	J4908, J9218, J9234	Ray Braswell – B. Wilson 500 kV; Ray Braaswell – Lakeover 500 kV
FAULT-8b	Ray Braswell - B. Wilson 500 kV	3 PH/SLG	5	9	765.3- j6686.74	J4920	J4928, J2230, J2233	J4917	Ray Braswell – B. Wilson 500 kV; Ray Braswell 500/230 kV transformer #1
FAULT-9a	Ray Braswell 500/ 115 kV Transformer #1	3 PH/SLG	5	9	765.3- j 6686.74	J4904	J4917	J2404, J2408, J4908	Ray Braswell 500/ 115 kV Transformer #1; Ray Braswell - Franklin 500 kV


Table 2-4 List of 3 PhaseStuck Brekaer (IPO: 3PH-1PH) faults simulated for stability analysis




CASE	LOCATION	ТҮРЕ	CLEARING (cycle		ME SLG FAULT S IMPEDANCE BR		PRIMARY BREAKER	SECONDARY BREAKER	TRIPPED FACILITIES	
			PRIMARY	Back- up	(MVA)	#	# TRIP #			
FAULT-9b	Ray Braswell 500/ 115 kV Transformer #1	3 PH/SLG	5	9	765.3- j6686.74	J4917	J4904	J4920	Ray Braswell 500/ 115 kV Transformer #1; Ray Braswell 500/230 kV transformer #1	
FAULT-10a	Ray Braswell 500/ 230 kV Transformer #1	3 PH/SLG	5	9	765.3- j6686.7 4	J4920	J4917	J4928, J2230, J2233	Ray Braswell 500/ 230 kV Transformer #1; Ray Braswell - B. Wilson 500 kV	
FAULT-10b	Ray Braswell 500/ 230 kV Transformer #1	3 PH/SLG	5	Ð	765.3- j6686.74	J4917	J4920	J4904	Ray Braswell 500/ 115 kV Transformer #1; Ray Braswell 500/230 kV transformer #1	
FAULT-11a	Franklin - McKinight 500 kV	3 PH/SLG	5	9	823.73- j5887.89	J2416	BRK#21105, BRK#21110, J2412	J2420, S4402, S4405	Franklin - McKinight 500 kV; Franklin - Bogal USA - Adams Creek 500 kV	
FAULT-11b	Franklin - McKinight 500 kV	3 PH/SLG	5	9	823.73- j5887.89	J2412	BRK#21105, BRK#21110, J2416	J2408	Franklin - McKinight 500 kV; Franklin 500/115 kV transformer #1	
FAULT-12a	Franklin - Bogal USA - Adams Creek 500 kV	3 PH/SLG	5	9	823.73- j5887.89	J2416	S4402, S4405, J2420	BRK #21105, BRK#21110, J2412	Franklin - Bogal USA - Adams Creek 500 kV; Franklin - McKnight 500 kV	
FAULT-12b	Franklin - Bogal USA - Adams Creek 500 kV	3 PH/SLG	5	9	823.73- j5887.89	J2420	S4402, S4405, J2416	J2420	Franklin - Bogal USA - Adams Creek 500 Kv; Franklin - G. Gulf 500 kV	
FAULT-13a	Franklin - Ray Braswell 500 kV	3 PH/SLG	5	9	823.73- j5887.89	J2404	J2408, J4904, J4908	J2425	Franklin - Ray Braswell 500 Kv, Franklin 500/115 kV transformer #1	
FAULT-13b	Franklin - Ray Braswell 500 kV	3 PH/SLG	5	9	823.73- j5887.89	J2408	J2404, J4908, J4904	J2412	Franklin - Ray Braswell 500 kV; Franklin 500/115 kV transformer #2	
FAULT-14a	Franklin - G. Gulf 500 kv	3 PH/SLG	5	9	823.73- j5887.89	J2425	J2420, J5248, J5240	J2404	Franklin - G. Gulf 500 kV; Franklin 500/115 kV transformer #1	
FAULT-14b	Franklin - G. Gulf 500 kv	3 PH/SLG	5	9	823.73- j5887.89	J2420	J5248, J5240, J2425	J2416, S4402, S4405	Franklin - G. Gulf 500 kV; Franklin - Bogal USA - Adams Creek 500 kV	
FAULT-15a	Franklin 500/115 kV transformer #1	3 PH/SLG	5	9	823.73- j5887.89	J2404	J2425	J2408, J4904, J4908	Franklin 500/115 kV transformer #1; Franklin - Ray Braswell 500 kV	
FAULT-15b	Franklin 500/115 kV transformer #1	3 PH/SLG	5	9	823.73- j5887.89	J2425	J2404	J2420, J5248, J5240	Franklin 500/115 kV transformer #1; Franklin - G. Gulf 500 kV	




ABB











ABB

		PRE-PID226		ST-PID226
CASE	Stable	Acceptable Voltages	Stable	Acceptable Voltages
CASE	?	?	?	?
	· · ·	•	•	· ·
FAULT-1		Not tested	Y	Y
FAULT-2		Not tested	Y	Y
FAULT-3		Not tested	Y	Y
FAULT-4		Not tested	Y	Y
FAULT-5		Not tested	Y	Y
FAULT-6		Not tested	Y	Y
FAULT-7		Not tested	Y	Y
FAULT-8		Not tested	Y	Y
FAULT-9		Not tested	Y	Y
FAULT-10		Not tested	Y	Y
FAULT-11		Not tested	Y	Y
FAULT-12		Not tested	Y	Y
FAULT-13		Not tested	Y	Y
FAULT-14		Not tested	Y	Y
FAULT-15		Not tested	Y	Y
FAULT-1a		Not tested	Y	Y
FAULT-2b		Not tested	Y	Y
FAULT-3a		Not tested	Y	Y
FAULT-3b		Not tested	Y	Y
FAULT-4a		Not tested	Y	Y
FAULT-4b		Not tested	Y	Y
FAULT-5a		Not tested	Y	Y
FAULT-6a		Not tested	¥	¥
FAULT-6b		Not tested	¥	¥
FAULT-7a		Not tested	¥	¥
FAULT-7b		Not tested	¥	¥
FAULT-8a		Not tested	¥	¥
FAULT-8b		Not tested	¥	¥
FAULT-9a		Not tested	¥	¥
FAULT-9b		Not tested	¥	¥
FAULT-10a		Not tested	¥	¥
FAULT-10b		Not tested	¥	¥
FAULT-11a		Not tested	Y	Y
FAULT-11b		Not tested	Y	Y
FAULT-12a		Not tested	Y	Y
FAULT-12b		Not tested	Y	Y
FAULT-13a		Not tested	Y	Y
FAULT-13b		Not tested	Y	Y
FAULT-14a		Not tested	Y	Y
FAULT-14b		Not tested	Y	Y
FAULT-15a		Not tested	Y	Y
FAULT-15b		Not tested	Y	Y

Table 2-5 Results of faults simulated for stability analysis



The system was found to be STABLE following all the simulated faults.

Figure 2-3 and Figure 2-4 show plots for the G. Gulf unit response and the voltage recovery at POI following two selected faults.

Transient Voltage Recovery

The voltages at all buses in the Entergy system (above 115 kV) were monitored during each of the fault cases as appropriate. No Voltage criteria violation was observed following a normally cleared three-phase fault.

As there are no specific voltage dip criteria for three-phase fault converted into singlephase stuck breaker faults, the results of these faults were compared with the most stringent voltage dip criteria - not to exceed 20 % for more than 20 cycles. After comparison against the voltage-criteria, no voltage criteria violation was observed with the proposed uprate of G. Gulf unit (PID-226) case.






Figure 2-3 PID-226 Machine parameters for FLT_1_3PH






Figure 2-4 PID-226 Machine parameters for Fault _14_3PH



2.4 CRITICAL CLEARING TIME ANALYSIS

Evaluation of Critical Clearing Time (CCT) was carried out for faults at G. Gulf 500 kV substation. Two 3 phase stuck breaker (IPO operation) faults - Fault 1a and Fault 2b - at G. Gulf 500 kV substation were considered.

The primary Clearing Time was kept equal to the normal value (5 cycles on 500 kV and 6 cycles on 230 kV) and the backup clearing time was varied to find the CCT.

Table 2-6 shows the Critical Clearing Times calculated for the simulated faults with PID-222. Figure 2-5 and Figure 2-6 shows the excursions in the speed of G. Gulf unit following the two faults for both, WITH and WITHOUT PID-226 project.

CASE		CCT (in cycles)						
	LOCATION	Primary	Back-up Clearing					
	LOCATION	clearing	WITHOUT PID-226	WITH PID-226				
FAULT_1a	G. Gulf - B. Wilson 500 kV	5	41	15				
FAULT_2b	G. Gulf - Franklin 500 kV	5	46	18				

Table 2-6: CCT Results

It can be seen from the results that the smallest CCT at G. Gulf 500 kV substation was 5 + 15 cycles for a fault involving loss of G. Gulf – B. Wilson 500 kV line. The lowest critical clearing time 20 cycles (=5 + 15 cycles) is still larger than Entergy's standard clearing time of14 cycles (= 5 + 9 cycles) for 500 kV breakers.

Based on the results of critical clearing time analysis it can be concluded that proposed PID-226 project (206 MW uprate of G. Gulf Unit#1) does not adversely impact the critical clearing at G. gulf 500 kV substation.



	POST-PID226 CASE
SIEMENS POWER	3PH-1PH G.GULF 500KV G.GULF - B.WILSON 500KV





Figure 2-5 Critical Clearing Time comparison following Fault 1a








Figure 2-6 Critical Clearing Time comparison following Fault 2b



15.03

0000

с Л

3 CONCLUSIONS

Southwest Power Pool, Inc (SPP) at the request of Entergy Services Inc. has commissioned ABB Inc. to perform a stability analysis for Facility study of PID-226, which is a request for 206 MW uprate of existing G. Gulf Unit #1 in the Entergy transmission system.

A system impact study for the PID-226 has previously been completed. The objective of this study was to supplement the stability analysis performed in the system impact study for PID-226 Project. To that end, selected faults at G. Gulf 500 kV substation were simulated and a Critical Clearing Time Analysis was performed at G. Gulf 500 kV substation. The study was performed on 2012 Summer Peak case, provided by SPP/Entergy.

The system was stable following all simulated normally cleared and stuck-breaker faults. No voltage criteria violation was observed following simulated faults.

The Critical Clearing times at G. Gulf 500 kV substations are within the capabilities of the existing protection systems. The smallest CCT at G. Gulf 500 kV substation was 5 + 15 cycles for a fault involving loss of G. Gulf – B. Wilson 500 kV.

Based on the results of stability analysis it can be concluded that proposed PID-226 project does not adversely impact the stability of the Entergy System in the local area. Also, PID-226 does not adversely impact the Critical Clearing time at G. Gulf 500 kV substations. Hence, no transmission reinforcements and/ or upgrades were identified for the interconnection of the PID-226 project.

The results of this analysis are based on available data and assumptions made at the time of conducting this study. If any of the data and/or assumptions made in developing the study model change, the results provided in this report may not apply.



APPENDIX A DATA PROVIDED BY CUSTOMER

Attachment A to Appendix 1 Interconnection Request

LARGE GENERATING FACILITY DATA

UNIT RATINGS

kVA <u>1600000</u> °F <u>95</u>	Voltage 22000
Power Factor 0.9 lag	
Speed (RPM) <u>1800</u>	Connection (e.g. Wye) <u>Wye</u>
Short Circuit Ratio0.75	Frequency, Hertz 60
Stator Amperes at Rated kVA	Field Volts
Max Turbine MW <u>1525</u> °F	95

COMBINED TURBINE-GENERATOR-EXCITER INERTIA DATA

Inertia Constant, H =	4.5112	kW sec/kVA
Moment-of-Inertia, $WR^2 =$	<u>9644006</u>	lb. ft. ²

REACTANCE DATA (PER UNIT-RATED KVA)

	DIRECT AXIS		QUADRATURE AXIS	
Synchronous – saturated Synchronous – unsaturated Transient – saturated Transient – unsaturated Subtransient – unsaturated Subtransient – unsaturated Negative Sequence – saturated Negative Sequence – unsaturated Zero Sequence – unsaturated Zero Sequence – unsaturated Leakage Reactance	$\begin{array}{c} X_{dv} \\ X_{di} \\ X'_{dv} \\ X'_{di} \\ X''_{di} \\ X''_{di} \\ X2_v \\ X2_i \\ X0_v \\ X0_i \\ Xl_m \end{array}$	1.292 1.551 0.380 0.417 0.243 0.288 0.249 0.295 0.181 0.151 0.245	$\begin{array}{c} X_{qv} \\ X_{qi}^{} \\ X'_{qv} \\ X'_{qi}^{} \\ X''_{qv} \\ X''_{qi} \\ X''_{qi} \end{array}$	$ \begin{array}{r} 1.258\\ 1.473\\ 0.751\\ 0.832\\ 0.255\\ 0.302 \end{array} $



FIELD TIME CONSTANT DATA (SEC)

Open Circuit	T' _{do}	6.286	T' _{go}	<u>0.382</u>
Three-Phase Short Circuit Transient	T' _{d3}	1.446	Ta	0.501
Line to Line Short Circuit Transient	T' _{d2}	2.062	4	
Line to Neutral Short Circuit Transient	T'_{d1}	2.211		
Short Circuit Subtransient	T"d	0.030	T"a	0.043
Open Circuit Subtransient	T" _{do}	0.047	T" _{qo}	0.123

ARMATURE TIME CONSTANT DATA (SEC)

Three Phase Short Circuit	T_{a3}	0.361
Line to Line Short Circuit	T _{a2}	0.361
Line to Neutral Short Circuit	Tal	0.314

NOTE: If requested information is not applicable, indicate by marking "N/A."

MW CAPABILITY AND PLANT CONFIGURATION LARGE GENERATING FACILITY DATA

ARMATURE WINDING RESISTANCE DATA (PER UNIT)

Positive	\mathbf{R}_1	0.003656
Negative	R_2	0.04775
Zero	R_0	0.00253

Rotor Short Time Thermal Capacity $I_2^2 t = \underline{5.47}$ Field Current at Rated kVA, Armature Voltage and PF = <u>8580</u> amps Field Current at Rated kVA and Armature Voltage, $0 \text{ PF} = \underline{11400}$ amps Three Phase Armature Winding Capacitance = <u>1.464</u> microfarad Field Winding Resistance = <u>0.0405</u> ohms <u>20</u> °C Armature Winding Resistance (Per Phase) = <u>0.0004794</u> ohms <u>20</u> °C



CURVES

Provide Saturation, Vee, Reactive Capability, Capacity Temperature Correction curves. Designate normal and emergency Hydrogen Pressure operating range for multiple curves.

Please refer to Attachment 1.

GENERATOR STEP-UP TRANSFORMER DATA RATINGS

Capacity Self-cooled/Maximum Nameplate <u>1650000</u> / <u>1650000</u> kVA Voltage Ratio(Generator Side/System side/Tertiary) <u>20.9</u> / <u>500</u> / <u>none</u> kV

Fixed Taps Available +7.5% / +5% / +2.5% / 0 / -2.5%

Present Tap Setting Nominal

IMPEDANCE

Positive	Z1 (on self-cooled kVA rating)_	0.1627	%	46.41	X/R
Zero	Z ₀ (on self-cooled kVA rating)_	0.1627	%	46.41	X/R



EXCITATION SYSTEM DATA

Identify appropriate IEEE model block diagram of excitation system and power system stabilizer (PSS) for computer representation in power system stability simulations and the corresponding excitation system and PSS constants for use in the model.

Please refer to attachment 2.

GOVERNOR SYSTEM DATA

Identify appropriate IEEE model block diagram of governor system for computer representation in power system stability simulations and the corresponding governor system constants for use in the model.

Please refer to attachment 3.

WIND GENERATORS

Number of generators to be interconnected pursuant to this Interconnection Request:

Elevation: _____ Single Phase ____ Three Phase

Inverter manufacturer, model name, number, and version:

List of adjustable setpoints for the protective equipment or software:

Note: A completed General Electric Company Power Systems Load Flow (PSLF) data sheet or other compatible formats, such as IEEE and PTI power flow models, must be supplied with the Interconnection Request. If other data sheets are more appropriate to the proposed device, then they shall be provided and discussed at Scoping Meeting.



INDUCTION GENERATORS

(*) Field Volts:

(*) Field Amperes:

(*) Motoring Power (kW):

(*) Neutral Grounding Resistor (If Applicable):

(*) I₂²t or K (Heating Time Constant):

(*) Rotor Resistance:

(*) Stator Resistance: _____

(*) Stator Reactance:

(*) Rotor Reactance:

(*) Magnetizing Reactance:

(*) Short Circuit Reactance:

(*) Exciting Current:

(*) Temperature Rise:

(*) Frame Size: _____

(*) Design Letter: ____

(*) Reactive Power Required In Vars (No Load):

(*) Reactive Power Required In Vars (Full Load):


(*) Total Rotating Inertia, H: _____ Per Unit on KVA Base

Note: Please consult Transmission Provider prior to submitting the Interconnection Request to determine if the information designated by (*) is required.






Grand Gulf 1 - Uprate










GENERATOR

V-Curves at Rated Voltage






ATTACHMENT 2 Sheet 1 of 5

GRAND GULF

IEEE TYPE AC5A EXCITATION	SYSTEM MODEL DATA
$K_{\rm A} = 600 {\rm p.u.}$	$T_{A} = 0.10$ sec.
$K_{\rm F} = 0.02 {\rm p.u.}$	$T_{F1} = 1.0$ sec.
$T_{F2} = 0.13$ sec.	$T_{F3} = 0$
$T_{\rm E} = 0.22$ sec.	$T_R = 0.2$ sec.
$S_{\rm El} = 0.73$	$EFD_1 = 3.7 p.u.$
$S_{E2} = 0.73$	$EFD_2 = 2.8 p.u.$
$K_{\rm E} = 1.0 \rm p.u.$	
V _{Rmax} = 6.4 p.u.	$V_{Rmin} = -6.4 \text{ p.u.}$



IEEE Type AC5A Excitation System Model

Reference: IEEE Standard 421.5-2005, "IEEE Recommended Practice for Excitation System Models for Power System Stability Studies"

Excitation system model data 061120. By J.D. Hurley. 12-7153. 12-7154.doc Printed: 12/7/2006 2:02:21 PM

Siemens Westinghouse Confidential



ATTACHMENT 2 Sheet 2 of 5

Power Technologies, Inc.


Exciter and Governor Model Data Sheets

	5 ,				
			IEEE T	ESAC5A ype AC5A Excitation System	-
machine	el is located at el uses CONs			# IBUS, # I. # J,	
CONs	#	Value	Description		
J	-	and the design of the second s	T _R (Seconds)	ECOMP	
J+1			KA	VOTHSG	
J+2		0.1	T _A (Seconds)	VUEL ESAC5A EF	o
J+3		6.4	V RMAX Or Zero	and the second sec	
J+4		-6.4	V RMN	VOEL	
J+5		1	K E Or Zero		
J+6		0.22	T _E > 0 (Seconds)		
J+7		0.02	K _F		
J+8		1.0	T _{F1} > 0 (Seconds)		
J+9			T F2 (Seconds)		
J+10			T _{F3} (Seconds)		
J+11			Eı		
J+12		0.73	S _E (E ₁)		

IBUS, 'ESAC5A', I, TR, KA, TA, VRMAX, VRMIN, KE, TE, KF, TF1, TF2, TF3, E1, SE(E1), E2, SE(E2)/

2.8 E 2

0.73 SE(E2)



PSS/E 25

J+13

J+14

Program Operation Manual - Volume II VI-13

Page 1 of 1


ESAC5A-GrandGulf.xls

Site Specific Planning Model Inputs

ATTACHMENT 2 Sheet 3 of 5

SIEMENS

Excitation System Thyrisiem Computer Representation *)



1) According to IEEE



Fig.2.1.



ATTACHMENT 2 Sheet 4 of 5

Site Specific Planning Model Inputs

Steam Turbine Model for System Dynamic Studies for Grand Gulf

۴. ۲ T_{C0} = 2.75s Sierbens PG P11M3, Bennauer, 21 June 2005 <u>_</u>___ ∢ nulation started (pU) 2 : 0.35 = 0.25s : 0.65 Turbine $1+sT_{cc}$ P_M = Mechanical Power Steam Power Limits imposed by Valve: ٥Ĉ Limits on Rate of Change of Po Control Valve Rate Limits: P_u HP Turbine Load Fraction F HP Turbine Time Constant 1 LP Turbine Load Fraction F LP Turbine and Cross-over F Power at Valve Outlet when Sim [₽] P_o = Initial Power v P_{ov} = Power at Val $\frac{1}{1+sT_{CH}}$. . °§ zee: "Dynamic Models for Sheam and Hydro Turbines in Power System Studies". IEEE Committee Report. 1873 No Consideration of Moreinearities of Main Steam Control Valve. IP-Valve Is £101 open. Pww 74 FLu. = -1 pU FLm = 1 pU 1.5 Down tă î ponse Low L ponse High L $K_V = 20$ $T_3 = 1.5s$ $T_3 = 0.15s$ R₁ = 0.05 ₹ Speed deviation ū Position-Controller Gain Control Valve Time Constant (Fast closing Res -12 g FL ₽₽ ₽₽ പ് Ē ã



ABB



ABB

ATTACHMENT 3 Sheet 1 of 2

Power Technologies, Inc.

Exciter and Governor Model Data Sheets

IEEEG1

IEEE Type 1 Speed-Governing Model

This model is located at system bus	#
machine	#
This Mmodel may be located at system bus	#
machine	#
This model uses CONs starting with	#

NOTE: JBUS and JM are set to zero for non-cross compound.

	10001
#	1.
#	0 JBUS,
#	0 M.
#	J,
is is	a non-cross compound unit)

IBUS,

CONs	*	Value	Description		
J		12	κ.		
J+1		0	T1 (Seconds)		
J+2		0	T ₂ (Seconds)		
J+3		0.075	T ₃ (>0)(Seconds)		
J+4		0.60	U _o (p.u./Seconds)		
J+5		-0.60	U _C (<0.)(p.u./Seconds)		
J+6		0.9	PMAX(p.u. on Machine		
			MVA Rating)		
J+7		0	P _{MIN} (p.u. on Machine		
			MVA Rating)		
J+8		0.25	T ₄ (Seconds)		
J+9		0.35	K ₁		
J+10		0	K ₂		
J+11			T ₅ (Seconds)		
J+12		0.65	K ₃		
J+13		0	K4		
J+14		0	T ₆ (Seconds)		
J+15		0	K ₅		
J+16		0	K ₆		
J+17		0	T7(Seconds)		
J+18		0	К7		
J+19		0	к _в		

(Note: this



Page 1 of 2

IEEEG1-Gov-GrandGulf-rev2.xls




ATTACHMENT 3 Sheet 2 of 2

Correct Model: Note that K3 is properly represented.


Gover: for Model Data Sheet; IEEEGI

Power Technologies, Inc.



Incorrect Model: Note that there are two blocks with K2 and no block with K3.

IBUS, 'IEEEG1', I, JBUS, M, K. T1, T2, T3, U6, Uc, PMAX, PMIN, T4, K1, K2, T5, K3, K4, T6, K5, K6, T7, K7, K6/



Page 2 of 2

IEEEG1-Gov-GrandGulf-rev2.xls



APPENDIX B LOAD FLOW AND STABILITY DATA IN PSSE FORMAT

Loadflow Data

336821,'1 ', 1544.000, 0.000, 330.000, -330.000,1.02000,336820, 1600.000, 0.003656, 0.2880, 0.00000, 0.00000,1.00000,1, 100.0, 1544.000, 150.000, 0.003656, 1,1.0000 1,1.0000 0 / END OF GENERATOR DATA, BEGIN BRANCH DATA 0 / END OF BRANCH DATA, BEGIN TRANSFORMER DATA 36820,336821, 0,'1 ',1,2,1, 0.00000, 0.00000,2,' 0.0035, 0.1627, 1650.00 1.00000, 0.000, 0.0000, 1650.00, 1650.00, 0, 1.07500, 0.97500, 5, 0, 0.00000, 0.00000 1.00000, 0.000 ',1, 1,1.0000 0, 1.07500, 0.97500, 1.00000, 0.000 0 / END OF TRANSFORMER DATA, BEGIN AREA DATA
0 / END OF AREA DATA, BEGIN TWO-TERMINAL DC DATA 0 / END OF TWO-TERMINAL DC DATA, BEGIN VSC DC LINE DATA 0 / END OF VSC DC LINE DATA, BEGIN SWITCHED SHUNT DATA 0 / END OF SWITCHED SHUNT DATA, BEGIN IMPEDANCE CORRECTION DATA 0 / END OF IMPEDANCE CORRECTION DATA, BEGIN MULTI-TERMINAL DC DATA 0 / END OF MULTI-TERMINAL DC DATA, $\stackrel{\scriptstyle \rm D}{\scriptstyle \rm BEGIN}$ MULTI-SECTION LINE DATA 0 / END OF MULTI-SECTION LINE DATA, BEGIN ZONE DATA 0 / END OF ZONE DATA, BEGIN INTER-AREA TRANSFER DATA / END OF INTER-AREA TRANSFER DATA, BEGIN OWNER DATA 0 0 / END OF OWNER DATA, BEGIN FACTS DEVICE DATA 0 / END OF FACTS DEVICE DATA **Dvnamics Data** REPORT FOR ALL MODELS BUS 336821 [GGULF 21.000] MODELS

** GENROU ** BUS X-- NAME --X BASEKV MC CONS STATES 336821 GGULF 21.000 1 130656-130669 51167-51172

 MBASE
 Z S O R C E
 X T R A N
 GENTAP

 1600.0
 0.00366+J 0.28800
 0.00000+J 0.00000
 1.00000

 T'D0
 T'Q0
 T'Q0
 H
 DAMP
 XD
 XQ
 X'D
 X'Q
 X'D
 XL

 6.29
 0.047
 0.38
 0.123
 4.51
 0.00
 1.5510
 1.4730
 0.4170
 0.8320
 0.2880
 0.2450

S(1.0) S(1.2) 0.2000 0.5000

** PSS2A ** BUS X-- NAME --X BASEKV MC CONS STATES VARS ICONS 336821 GGULF 21.000 1 130670-130686 51173-51188 8396-8399 4483-4488

IC1 REMBUS1 IC2 REMBUS2 M N 1 0 3 0 5 1 TW1 TW2 T6 TW3 TW4 T7 KS2 KS3 2.000 0.000 2.000 0.000 2.000 0.202 1.000

 T8
 T9
 KS1
 T1
 T2
 T3
 T4
 VSTMAX
 VSTMIN

 0.500
 0.100
 8.000
 0.150
 0.030
 0.150
 0.030
 0.100
 -0.100

** ESAC5A ** BUS X-- NAME --X BASEKV MC CONS STATES VAR 336821 GGULF 21.000 1 130687-130701 51189-51193 8400

 TR
 KA
 TA
 VRMAX
 VRMIN
 KE
 TE
 KF
 TF1
 TF2
 TF3

 0.200
 600.00
 0.100
 6.400
 -6.400
 1.000
 0.220
 0.020
 1.000
 0.130
 0.000

E1 S(E1) E2 S(E2) KE VAR 3.7000 0.7300 2.8000 0.7300 0.0000



** IEEEG			AMEX BASH 21.000			-		V A R S 3401-8402
ĸ	т1	т2		UC P			K1	
12.00	0.000	0.000	0.075 0.0	500 -0.600	0.9700 0.	.0000 0.	.250	0.350
К2	т5	K3	К4 Тб	К5	кб т7	К7	K8	3
0.000	2.750	0.650	0.000 0.0	0.000 0.000	0.000	0.000 0	0.000	0.000





F. PSS Sensitivity

GGNS EPU team had submitted typical data for EX2000 type Power System Stabilizer (PSS) represented by IEEE model PSS2A. Submission of PSS model is required by the LGIP, Attachment A to Appendix 1.

It is our understanding that PSS2A represents an accelerating power type PSS, which is standard in the GE EX2000 digital-based excitation systems. The existing excitation system of GGNS generator is type ESAC5A, which is a rotary excitation system with an analog voltage regulator. Installing a digital PSS with analog voltage regulator and rotary excitation system is not prudent, as it may provide very little benefit in controlling power system oscillations.

Installing a stand alone (after market) analog PSS which is not integral to analog excitation voltage regulator may lead to undesirable performance. This defeat the purpose of the PSS, which is a supplementary control system often applied as an integral part of excitation control system. The basic function of the PSS is to apply a signal to the excitation system, thereby creating electrical torques that damp out power oscillations. Additionally, Siemen's engineers were unable to provide operational data for proposed stand alone analog PSS as there are only two generators of the type of GGNS unit in the USA.

GGNS requested approval of the strategy to defer the installation of PSS until implementation of new digital voltage regulator upgrade. This may occur in 18 to 36 months after the implementation of EPU in Refueling Outage RF-18. According to GGNS personnel, new digital voltage regulator upgrade is currently being studied with the inclusion of a digital PSS as a part of the modification.

Based on GGNS's suggestion, ABB (Entergy Transmission's Consultant who had performed Stability Analysis for GGNS – EPU) was requested to perform sensitivity analysis for the proposed uprate with and without originally proposed PSS2A type power system stabilizer. Two of the most limiting faults were simulated without PSS:

- 1. Fault_1a: 5 + 9 cycles 3 phase stuck breaker fault (IPO breaker operation), cleared by tripping Grand Gulf Baxter Wilson 500 kV line
- 2. Fault_2b: 5 + 9 cycles 3 phase stuck breaker fault (IPO breaker operation), cleared by tripping Grand Gulf Franklin 500 kV line

The results indicated that the system would be stable following both faults. As expected, the damping of oscillations in the Grand Gulf unit following both the faults without PSS case was lower than that with the PSS case. However, post-fault performance of the Grand Gulf unit without the PSS was acceptable per Entergy's transmission planning criteria.

Entergy's Technical System Studies Group recommends deferring installation of PSS until implementation of new digital voltage regulator upgrade. The bases for recommendation are listed below:

- After the EPU the GGNS unit will be one of the largest generators in the USA. Alternative to deferral; installation of stand alone analog PSS lacks proven operational history. It is always desirable to use proven technologies with reasonable operational history during upgrades to ensure safe and reliable operation and to ensure required Nuclear Safety.
- The results of the simulations with and without PSS (sensitivity analysis performed by ABB) indicate satisfactory post-fault performance of the Grand Gulf unit in both scenarios which meets the requirements of transmission planning criteria.
- 3. Additionally, Policy Statement/Guidelines for Power System Stabilizers on the Entergy System states "In areas where a dynamic stability problem has not been explicitly identified, all synchronous generators (50 MVA and larger) will still be required to install stabilizers. However, in such cases the tuning will not be required and the stabilizer may remain disconnected until further advised by Entergy." Presently, based on the analysis performed by Entergy's consultant (ABB), the area surrounding the Grand Gulf has not exhibited any dynamic stability problem.

